



TÉCNICO
LISBOA

Production methodologies applied to the fluid system outfitting on a construction and repair shipyard

João José Ludovice Paixão de Melo

Thesis to obtain the Master of Science Degree in

Naval Architecture and Marine Engineering

Supervisors: Engenheiro Francisco Jorge Gomes Lopes

Professor Doutor Carlos Pancadas Guedes Soares

Examination Committee

Chairperson:

Supervisor: Engenheiro Francisco Jorge Gomes Lopes

Members of the Committee:

October 2018

Acknowledgments

Em primeiro lugar, quero expressar a minha gratidão ao meu orientador de tese, Professor Gomes Lopes, pelo apoio prestado na elaboração deste trabalho. A sua permanente disponibilidade, a orientação segura, as críticas construtivas e as sugestões valiosas permitiram torná-lo um verdadeiro processo de desenvolvimento pessoal e profissional. Gostaria também de agradecer ao Professor Doutor Carlos Guedes Soares e ao Professor Gomes Lopes, porque a pesquisa em que se baseou grande parte desta tese só foi possível graças à oportunidade que me deram de realizar a dissertação de mestrado no estaleiro da Atlantic Eagle Shipbuilding. Quero fazer um agradecimento especial ao Eng. Bruno Costa, ao Engenheiro Raul Leite e a toda a equipa da Atlantic Eagle Shipbuilding, por toda a disponibilidade para a recolha presencial de dados, no estaleiro, e por todos os documentos técnico fornecidos para a realização desta dissertação. Por fim, quero agradecer à minha família, em particular à minha mãe, pelo apoio incondicional que me garantiram em todos os momentos deste trabalho.

Abstract

Due to the competitiveness of shipbuilding environment, shipyards try to optimize production efficiencies in terms of time, costs and quality and obtaining better results.

Modular Outfitting (MO) is an approach that consists in the installation of outfit systems on a structural block prior to shipboard erection. Traditional Outfitting (TO) consist in on-board outfitting installation on a building berth before launching or on-board after launching and as it allows parallel assembly of various outfitting systems, it has the potential to reduce the assembling workload.

The dissertation scope is to compare the workload (expressed in man-hours - *Mh*) of a ferry vessel bilge's fluid system (Haksolok built in Atlantic Eagle Shipyard) assembly performed by TO *versus* MO.

Three questions are addressed regarding MO implementation versus TO in three selected bilge piping zones of higher complexity concerning: workload differences; layout changes and risk management

The workload, measured in man-hours, used in the assembling procedure by MO, represented a reduction of 549 Man-hours or a gain of 74% *versus* TO.

There are advantages in the new layout concerning distance between work stations, space for outfitting activities and outfitting work flow hub creation.

A risk assessment was performed, and the most critical risks were associated to: Design Process; Dimensional Control and Running Test in Shop Process; Module Transportation and Fitting on Block Process and On-block Assembly Fitting and Installing Process. The higher risk score regards Effective Schedule Coordination between Block and Module Block

To control the major risks a list of nine critical success factors was defined, being the qualification of the labor force and the update of the equipment, the most critical.

Keywords

Modular Outfitting, Integrated construction, zone outfitting, systematic layout planning, risk management critical success factors, piping, outfitting

Resumo

Devido à competitividade do ambiente da construção naval, os estaleiros navais tentam otimizar a eficiência da produção em termos de tempo, custos e qualidade.

O aprestamento modular (MO) consiste na instalação de sistemas e equipamentos num bloco estrutural antes da montagem do navio. O aprestamento tradicional (TO) consiste na instalação do equipamento a bordo do navio antes do lançamento (na doca/rampa ou a bordo após o lançamento). O MO tem o potencial de reduzir a carga de trabalho de montagem dado permitir a montagem paralela de vários sistemas de equipamentos.

O objectivo desta dissertação é comparar a carga de trabalho da instalação, medida em horas-homem de um sistema de esgoto de um ferry (navio Haksolok construído no estaleiro Atlantic Eagle) utilizada pelo método TO com a utilizada pelo método MO.

O estudo centrou-se em três questões relativas à implementação de MO versus TO em três zonas seleccionadas do Sistema de Esgoto devido a maior complexidade referentes às diferenças de carga de trabalho; às mudanças de arranjo geral do estaleiro e à gestão do risco.

Verificou-se que a carga de trabalho utilizada no procedimento de montagem por MO, representou uma redução de 549 horas-homem ou um ganho de 74% versus TO.

Foram identificadas vantagens no novo layout no que concerne à distância entre estações de trabalho, espaço para atividades de aprestamento e adequação da criação de pontos logísticos para aprestamento.

Os riscos mais críticos foram os associados a: processo de design; controlo dimensional e teste de funcionamento no processo de manufactura; transporte dos módulos, montagem nos blocos, processo de instalação e montagem no bloco. O maior factor de risco correspondeu à coordenação do planeamento de montagem entre módulo e bloco.

Para controlar os principais riscos foi definida uma lista de nove factores críticos de sucesso, sendo os mais críticos, a qualificação da força de trabalho e a actualização do equipamento.

Palavras Chave

Aprestamento por construção modular, construção naval integrada, aprestamento por zonas, *systematic layout planning*, gestão de risco, factores críticos de sucesso, encanamentos, aprestamento

Contents

1	Introduction.....	2
1.1	Dissertation’s scope of work	4
1.2	Portuguese shipbuilding and ship repair	6
1.2.1	Portuguese Shipyards	6
1.2.2	Atlanticeagle Shipbuilding (AES).....	7
1.3	Haksolok ferry vessel	8
2	Behind State of Art.....	11
2.1	Preliminary concepts on ships life cycle	13
2.2	Outfitting	15
2.2.1	Traditional Outfitting	16
2.2.2	Modular Outfitting	16
2.2.3	Modular Outfitting advantages compared to Traditional Outfitting	20
2.3	Systematic Layout Planning (SLP).....	22
2.3.1	Phases of layout planning	23
2.3.2	Layout Developments	25
2.3.3	Layout Selection and Readjustments	26
2.4	Risk Management	28
3	Comparison between man hours using Traditional Outfitting and Modular Outfitting .	31
3.1	Problem Modeling	33
3.2	Analysis Methodology	33
3.2.1	Selection of the bilge system zones for Modular Outfitting implementation	34
3.2.2	Calculation of outfitting assembly Man-hours.....	35
3.3	Results and Analysis.....	45
4	Systematic Layout Planning for Modular Outfitting	53
4.1	Problem Modeling	55
4.2	Methodology.....	55
4.3	Shipyards layout changes and results	57
4.3.1	Factor analysis.....	57
4.3.2	Layout changes - Advantages <i>versus</i> Disadvantages	58
4.3.3	Cost Comparison	60
5	Modular Outfitting Implementation Risk Management.....	65
5.1	Scope of the problem	67
5.2	Methodology.....	67
5.2.1	Risk Identification.....	67
5.2.2	Qualitative Analysis	69
5.2.3	Risk Response.....	71
5.2.4	Critical Success Factors (CSFs).....	71
5.3	Results Analysis	71
5.3.1	Identified Risks	71
5.3.2	Qualitative Analysis	71
5.3.3	Risk Response.....	77
5.3.4	Critical Success Factors	79
6	Conclusion	81
6.1	Conclusions.....	83
6.2	Future Work.....	85
6.3	Bibliographic References	86
7	Annex A - Pipe notation and calculation factors and final results in <i>Mh</i>	
8	Annex B - Space relationship diagrams	
9	Annex C - Risk analysis and risk responses	

List of Figures

- Figure 1-1 Haksolok side view sketch 8
- Figure 2-1: MacGregor Ship’s cost influence curve according to life cycle phase..... 14
- Figure 2-2: Integrated outfitting assembly 18
- Figure 2-3: Allocated resources (line width scale) allocated in TO assembly 21
- Figure 2-4: Allocated resources (line width scale) allocated in MO assembly 21
- Figure 2-5: PQRST key to unlock layout problems 22
- Figure 2-6: The phases of systematic layout plan..... 23
- Figure 2-7: Stages of SLP 24
- Figure 2-8: Example of relationship chart..... 25
- Figure 3-1: Example that illustrates the 4 levels of the WBS codification used 35
- Figure 3-2: Traditional outfitting calculation variables 36
- Figure 3-3: Man-hours used for pipe assembly process by TO or MO 47
- Figure 3-4: Man-hours used for the assembly of each pipe section by TO or MO 49
- Figure 3-5: Modular outfitting zone number 1 51
- Figure 3-6: Modular outfitting zone number 1, 3D model and Modular outfitting zone number 1, on site photo..... 52
- Figure 4-1: Layout study process 56
- Figure 4-2: Existing TO layout relationship chart 61
- Figure 4-3: Suggested MO layout relationship chart..... 62
- Figure 4-4: Suggested MO module assembly flow chart 64
- Figure 4-5: Suggested MO module structure assembly flow chart 64
- Figure 5-1: Modular Outfitting workflow 68

List of Tables

Table 1-1 Ferry's general characteristics	8
Table 2-1: Modularized units according to their equipment complexity	20
Table 2-2: (Dis)Advantages letter and numerical coding	27
Table 3-1: Defined zones for Modular Outfitting, number of sections and location	34
Table 3-2: Straight pipe repairing Man-hours per meter	37
Table 3-3: Pipe's Curves and Branches coefficients.....	38
Table 3-4: Equipment installing coefficient.....	39
Table 3-5: Value of C_{loc} depending on specific pipe position for a tanker ship	40
Table 3-6: OECD A and B factors (coefficients) of influence per ship type and per ship size	41
Table 3-7: 1999 DWT shipped by the worldwide tanker fleet segmented by ship's DWT	42
Table 3-8: Unitary straight pipe manufacturing Man-hours	42
Table 3-9: CGT tanker and Ro-Ro values.....	45
Table 3-10: MO versus TO - Man-hours (Mh) reduction	45
Table 3-11: More complex and least complex Pipe sections description	46
Table 3-12: Summed results of MO and TO assembly Mh	47
Table 4-1: Advantages vs disadvantages analysis for the changing of the cutting machine position ..	58
Table 4-2: Advantages vs disadvantages analysis of the new outfitting shop.....	58
Table 4-3: MO/TO advantages against disadvantages weigh	59
Table 4-4: Trip distances between workstations	63
Table 4-5: Traveling times between workstations	63
Table 5-1: Example of a PMBOOK Impact-Likelihood table	70
Table 5-2: Design Process Identified Risks.....	72
Table 5-3: Identified Risks of Module Parts Manufactured	73
Table 5-4: Module Assembly Identified Risks	73
Table 5-5: Dimensional Control and Running Tests in Shop Identified Risks.....	74
Table 5-6: Transportation and Fitting On-Block Identified Risks.....	75
Table 5-7: On-Block Assembly Identified Risks	76
Table 5-8: Final trials identified risks	76
Table 5-9: 27 Identified risks likelihood-impact table	78

Acronyms

AER1	Auxiliary Equipment Room 1
AER2	Auxiliary Equipment Room 2
AER3	Auxiliary Equipment Room 3
AES	Atlantic Eagle Shipbuilding
CAD	Computer Aided Design
CGT	Compensated Gross Tonnage
CSF	Critical Success Factors
DWT	Deadweight
DN	Nominal Diameter
ENP	Estaleiros Navais de Peniche
ER	Engine Room
GT	Gross Tonnage
HBCM	Hull Block construction Method
IHI	Ishihawajima-Harima Heavy Industries
MO	Modular Outfitting
NSRP	National Shipbuilding Research Program
OECD	Organisation for Economic Co-operation and Development
OLS	Ordinary Least Squares
PMBOK	Project Management Body of Knowledge
PWBS	Product orientated Work Breakdown Structure
SLP	Systematic Layout Planning
SNAME	Society of Naval Architects and Marine Engineers
TNSW	Thyssen Nordseewerke
TO	Traditional Outfitting
WBS	Work Breakdown Structure
WWII	World War II
ZOFM	Zone Outfitting Method
ZPTM	Zone Painting Method

1

1 Introduction

Contents

1.1	Dissertation's scope of work.....	4
1.2	Portuguese shipbuilding and ship repair	6
1.3	Haksolok ferry Vessel.....	8

Due to the competitiveness of the shipbuilding business environment, shipyards are always trying to optimize their production efficiencies in terms of time, costs and quality, or in other words, to do more with the same (or less) resources and obtaining better results.

One of the methodologies used to increase shipbuilding effectiveness is Modular Outfitting (MO) approach.

Currently experts recommend the use of modular outfitting as a way of increasing efficiency and competitiveness in shipbuilding comparatively to Traditional Outfitting (TO).

As defined by Rubesa [1], Ship modular outfitting is defined as “the installation of outfit systems and components on a structural block or outfit unit prior to shipboard erection” and “Traditional Outfitting process corresponds to on-board outfitting installation on a building berth before launching or on-board after launching”.

Modular Outfitting methodology (as known as modular outfitting approach) allows the parallel assembly of various outfitting systems, which has the potential to reduce the assembling Man-hours and assembly time, when compared with traditional outfitting. [1]

1.1 Dissertation’s scope of work

The dissertation scope of work is to analyze a ferry vessel bilge’s fluid system assembly performed by traditional outfitting production methodology, their inputs and outputs and to compare them with the estimations of the equivalent parameters of fluid systems assembly performed by modular outfitting production methodology.

A Ferry type vessel (Haksolok) for the Democratic Republic of East-Timor is under construction using traditional outfitting at Atlantic Eagle Shipbuilding (AES) shipyard and is to be commissioned in 2018.

This study was made in collaboration with AES.

The data, concerning the assembly, installing and fitting by traditional outfitting used in this dissertation, was mainly collected from the AES pre-existing documents, from technical drawings and from field construction operations analysis. The data concerning modular outfitting alternative was based on information referred in the existing literature and on information collected on site from the production study (traditional outfitting data).

This study addresses three questions:

- i. The workload differences between traditional outfitting on-board approach and modular outfitting on-block approach.**
- ii. The potential layout changes required by the implementation of modular outfitting processes versus the implementation of traditional outfitting process according to Systematic Layout Planning (SLP) analysis.**
- iii. The risk management of modular outfitting approach implementation.**

For each question **specific objectives** were defined.

Regarding the first question, the primary objective was to **compare the Man-hours used** in production in the traditional on-board outfitting method with the Man-hours used in modular on-block outfitting method.

This analysis was circumscribed to selected bilge piping zones of higher outfitting complexity for which an increase in production efficiency could represent a significant decrease of workload.

The determinants considered for the workload calculation were the piping properties, namely: dimension, shape, location and position inside of the ship. The methodology is explained in detail in chapter 3.

Regarding the second question, the primary objective was to **compare the distances and routes** of the existing layout *versus* the distances and routes of the modular outfitting adapted layout.

Regarding the third question, the primary objectives were **to identify and manage the risks** associated to modular outfitting implementation, and to define the Critical Success Factors (CSFs) for effective implementation of modular outfitting approach.

Each of the three questions was addressed in a dedicated chapter (chapter 3, 4 and 5) and all chapters have a similar organizational structure.

1.2 Portuguese shipbuilding and ship repair

1.2.1 Portuguese Shipyards

Portuguese shipbuilding and ship repair business has several small/medium and one large shipyard. The shipyards are briefly described below according to the information published on their websites.

West Sea - Estaleiros Navais de Viana do Castelo - located on the northern part of the Portuguese coast, West Sea is now the biggest construction shipyard in Portugal, having great expertise and experience in what concerns the shipbuilding activity.

West Sea yard has as infrastructures two drydocks with 203 and 127 meters of length.

Recently they were acquired by Martifer Metalic Constructions and have been building inland waters cruise vessels for the river Douro and one naval ship.

Ship repair activities and construction of large steel structures are also performed in this shipyard.

Navalria - is a small shipyard located in Aveiro that used to be a fishing vessel focused shipyard. As occurred with West Sea, Navalria was also acquired by Martifer Metalic Constructions and operates in shipbuilding, ship repair and in the construction of large steel structures.

Navalria also repairs other smaller fishing vessels, working boats and historical ships. In terms of facilities is important to mention the existence of a drydock, of a floating dock and of a syncrolift.

Estaleiros Navais de Peniche (ENP) - is a shipyard located in Peniche, that operates in shipbuilding and ship repair of small size vessels. This yard gain reputation on the construction of composite fishing vessels, although in recent years it has also built passenger ships and working boats.

Navalrocha - is a repair shipyard located in Lisboa. This shipyard belongs to a group of different share holders and managed by ETE Group (Empresa de Trafego e Estiva) and has a great experience in maintenance and repair works in all types of ships and can docks ships in the two medium size graving docks.

NavalTagus - is a shipyard that also belongs to Grupo ETE and operates in shipbuilding and ship repair of small dimension vessels. Concerning shipbuilding activity, this yard has launched a tug boat in 2016. In repair business, NavalTagus, maintains inland waters barges, small dimension cargo ships and passenger ships. This shipyard has two longitudinal ramps.

Lisnave Estaleiros Navais - is a southern shipyard located in Mitrena, Setúbal. This is one of the biggest repair shipyards in Europe. Its major income activity is ship repair.

Lisnave's most remarkable assets are its dry docks. Having three large dimension drydocks: drydock 20, 21 and 22, with a respective length of over 400 meters, 350 meters and 300 meters.

Besides the main drydocks, Lisnave has three drydocks within an Hydrolift system with capacity to receive up to Panamax type vessels.

Lisnave repairs around 100 vessels per year and has a regular client portfolio from more than 50 countries.

This enterprise was founded in 1961 and in the past used to operate first in Rocha Shipyard (now explored by Naval Rocha) and from the early 1970's until 1999 it had operated in Margueira's yard. From the early seventies to the turning of the XX century Lisnave repaired some of the largest vessels operating worldwide including the French ULCCs (ultra large crude carrier) "Pierre Guillaumat" and "Batillus" and including also the "Seawise Giant", the largest vessel ever built.

Margueira's yard had drydock 13 that during the 1970's was considered the world's large drydock, could dock up to 1 000 000 tons of deadweight.

Nautiber - is a shipyard located on the shore of Guadiana River, near the city of Vila Real de Santo António, in Algarve. The shipyard's areas of expertise are the shipbuilding and ship repair of vessels built in fiberglass and wooden made. The major part of their vessel portfolio is building and repair fishing vessels.

1.2.2 Atlanticeagle Shipbuilding (AES)

Atlanticeagle Shipbuilding (AES) is a construction and repair shipyard located near the city of Figueira da Foz.

According to AES website (<http://aeshipbuilding.com/pt/about-us/our-history/>), this shipyard was founded in 1947 under *Estaleiros Navais do Mondego*.

During the XX century this shipyard gain recognition especially due to the construction of fishing vessels and passenger's aluminium catamarans ferries. During the same century a large number of other vessels besides fishing ships, were built including tug boats, general cargo boats, and others.

In 2012, the shipyard was acquired by new owners, having changed the name to Atlantic Eagle Shipbuilding.

Nowadays several projects are being developed both on shipbuilding and ship repair, being one of the most remarkable, the construction of a ferry vessel "Haksolok" for the *Autoridade da Região Administrativa Especial de Oé-Cusse Ambeno, Timor Leste*.

1.3 Haksolok ferry vessel

The analysis for the implementation of modular outfitting approach was made upon a ferry vessel bilge system, named Haksolok and built in AES (figure 1.1).

This specialized vessel was made to operate between islands, in small ports and piers, with shallow waters. To properly sail in those conditions, the vessel is highly maneuverable and has a medium value cruising speed.



Figure 1-1 Haksolok side view sketch

Table 1.1 summarize the general Ferry's characteristics, according to the information provided by the shipyard.

Characteristics	Measure	Units
Length overall (LOA)	71.3	m
Length between perpendiculars (Lpp)	59.34	m
Breadth Moulded (B)	12.6	m
Depth to Main Deck (D)	6.3	m
Design Draught (T)	3.6	m
Displacement (Δ)	1645	Ton
Cruising Speed	15	Knots
Pax	377	
Cars	25	

Table 1-1 Ferry's general characteristics

Characteristics	Measure	Units
Length overall (LOA)	71.3	m
Length between perpendiculars (Lpp)	59.34	m
Breadth Moulded (B)	12.6	m
Depth to Main Deck (D)	6.3	m
Design Draught (T)	3.6	m
Displacement (Δ)	1645	Ton
Cruising Speed	15	Knots
Pax	377	
Cars	25	

Regarding the outfitting method, during out the construction of Haksolok an on-board Traditional Outfitting method was carried on through the entire construction process

In traditional outfitting, all the pipes sections and valves are transported to the ship's inner spaces (double-bottom, hull and other enclosed areas) after all blocks had been erected.

It is important to mention that, in modular outfitting, some equipment components such as pumps, valves and filters are placed inside the vessel's blocks before block erection

2

2 Behind State of Art

Contents

2.1 Preliminary concepts on ships life cycle	12
2.2 Modular Outfitting	14
2.3 Systematic Layout Planning (SLP)	21
2.4 Risk Management	27

This chapter introduces the main theoretical concepts about Modular Outfitting production methodology, systematic layout planning and risk analysis, that will be applied in this study.

2.1 Preliminary concepts on ships life cycle

The ship's life cycle theoretical concepts are introduced because they will be used to define the identified risks of modular outfitting implementation Risk Analysis.

There are several ships' project life cycle model descriptions in the literature. This study adapted the Chapman and Ward [2] model that divides the project life cycle in to four major phases: conceptual phase, planning phase, execution phase and termination phase (that is a risk management orientated approach).

In this dissertation four ship's life cycle phases were defined in accordance to the location of its development

- **Design Develop and Engineering phase** corresponds to the merge of Conceptual phase and Planning phase as they are developed in a ship design office
- **Construction phase** corresponds to Execution phase that is carried out on shipyard.
- **Operation and Maintenance phase** corresponds to Termination phase is directly executed on board or on dock.
- **Scrapping phase** performed in a scrapping yard, was added to the project life cycle due to its contribution to financial accounting (revenue).

Each of the vessel's life cycle phases listed above has a specific impact on costs.

A visual representation of the vessel's life cycle phases, it's cost influence potential and the proportional contribution to final costs is displayed in Figure 2.1.




Figure 2-1: MacGregor Ship's cost influence curve according to life cycle phase

Adapted from Gomes Lopes [3]

Design Development and Engineering - Conceptual Phase

The decisions taken at this phase are key cost determinants, because during this phase the main characteristics of the vessel are settled in order to meet the requirements of the ship mission and of the stakeholders (shipowners and authorities).

This set of characteristics will define the ship namely in what concerns dimensions, capacity, speed and shipyard construction support facilities. These decisions should be definitive. Any subsequent changes (4) to these fundamental characteristics will determine substantial additional costs.

Design Development and Engineering - Planning Phase

This phase includes designing of the vessel, planning of the strategy and allocation of the resources.

The designing of the vessel includes all the design steps, from basic design up to design evaluation and vessel's performance criteria.

The planning of the strategy consists of defining deadlines and milestones.

Finally, the resource allocation sub-phase incorporates the estimation of resources to be used, as for example: the quantity of steel plates to be used for the structural blocks manufacturing.

Construction Phase

It is a phase with an important cost impact magnitude that depends on the compliance requirements regarding:

- The ship design phase decisions and with guidelines respecting the established scope of the work

- The quality control guidelines and therefore, assuring that the manufacturing/sub-assembly/assembly of pieces, systems and structures are in accordance with the quality standards (ISO 9001)
- The quality control guidelines and therefore, assuring that the painting and blasting procedures for pieces, systems and structures are in accordance with the quality standards (ISO 9001)
- The established deadlines and schedule between shipowner, classification society and shipyard

Any delay, namely due to correcting actions, potentially influences the start of ship's activity and its life costs.

Operation and Maintenance Phase

This phase influences the ship's life costs in a lesser order of magnitude than the previous mentioned ship cycle phases. Operation Phase corresponds to the period of the ship's life cycle on which revenues will be made. Therefore, without unexpected severe irregularities, the costs tend to be proportional to the ship's operating activity (length of legs, weather condition, and equipment's efficiency decrease due to usage).

Maintenance phase implies ship dry-docking and surveys and as it implies the stoppage of the vessel, it represents additional costs on top of the costs of the maintenance and repair works (replacing of steel components, replacing of equipment and machinery, blasting, painting, tank cleaning, and others).

Scrapping phase

This phase will bring a marginal increase of costs and has a low influence on the life cycle costs.

2.2 Outfitting

Shipbuilding is one-of-a-kind production process and a worldwide business, with a great number of players and stakeholders; therefore, it is a very competitive market segment.

The building yards, to keep up with their competitors, are always improving their production methods, so that they can produce more, within better quality standards and using fewer resources. This production improvement is achieved by developing methodologies that increase time efficiency of every task of the ship construction process without disregarding compliance with the classification societies rules.

One of the most time-consuming activities in ship construction is outfit manufacturing, assembling and fitting. "Outfit corresponds to all non-structural equipment and systems which are to be installed in or on a ship, including machinery" as per Rubesa definition [1]. Outfit assembling, or outfitting, is performed in almost every ship construction phase, which enhances costs across the whole construction process.

2.2.1 Traditional Outfitting

Traditionally, outfitting is a late stage process performed when the ship is on the erection berth or when the ship was on the pier after launching [1]. Outfit is assembled posteriorly to block grand assembly. Due to the space constraints resulting from the hull structure and vessel tanks, this process is carried in very confined spaces. This implies the usage of a large number of Man-hours for outfit elements transportation and fitting. Due to the space confinements many outfit units might have to be refitted which implies reworking, hence, wasting time, changing planned system layout and generating lower production indexes.

One of the methodologies developed to respond to the costly traditional outfitting process was the modular outfitting approach.

2.2.2 Modular Outfitting

Modular outfitting approach is an interim process of early sub-assembling of small components into modular units (modules) and to further away, assembling these modules in parallel with different specific stages of the ship construction process enabling construction time decrease [1].

This construction process also allows the implementation of the best layout for the systems function considering upfront the hull structure space constraints and reducing the need for on-board assembly adjustments. It however requires a larger space margin to pass through the equipment towards his berth.

One of the landmarks of modular construction was as the case of the Thyssen 1700 TEUs container vessel (described by Baade in [5]), which was the pioneer in applying modular construction methods to ship engine room and in achieving a significant construction reduction of cost within a shorter schedule time frame. Thyssen improved time efficiency by using the solution of modularization of large engine room sections without increasing significantly the area allocated to insert pre-assembled units into the engine room. This outcome has validated the efficiency of engine room modularization in terms of time and costs, within reasonable space margins.

As stated by Rubesa [1], "Modular Outfitting approach is based upon pre-outfitting in the workshop". This means that outfitting must start at an early design stage and must be integrated with the design (parallel design) of the numerous ship's areas, systems and structures. The parallel design of outfitting units is of the most importance towards the above-mentioned efficiency goal. This design methodology is applicable to equipment and systems, which compound the machinery to be positioned inside the ship. In summary, machinery design process must be done in parallel with the outfitting design to identify the maximum amount of equipment and outfitting components that can be assembled simultaneously in workshops.

The implementation of modular outfitting implies that ship construction has to be managed in an integrated approach to ensure effective planning, coordination of the workstations and coordination of processes towards delivering the necessary output in a synchronized and timely manner. The requirements of integrated construction solution demanded the development of engineering design

and of supporting equipment and software, a more sophisticated work scheduling and more complex system of standardized operating procedures regarding outfit construction and assembly. To comply with the demands of integrated construction process and modular outfitting approach, nowadays the usage of simulation software has been widespread along shipyards [7], preventing errors, rework and added costs.

2.2.2.1 Modular Outfitting Evolution and Implementation

Modular outfitting methodologies resulted from several improvements regarding organizational theories, equipment and materials as well as supporting design systems derived from the creation of Computer Aided Design (CAD) software, simulation software and management software.

Prior to World War II (WWII) new kind of practices started to be developed and were implemented afterwards [8] from the production revolution induced by WWII on. The most remarkable improvement among the new practices, such as the introduction of standardized procedures and design simplification, was the construction of ships by using block assembling. This practice was implemented in the US by Henry Kaiser's introduction of Group Technology. Further away Helmer Hann, a former Kaiser's employee, took these practices to a Japanese Industry enterprise named Industries Ishihawajima-Harima Heavy Industries (IHI). Based on the acquired know-how, IHI not only implemented these practices into their manufacturing systems, but also further developed and changed the concept of shipbuilding, creating a new work organization called Production Work Breakdown System (Product orientated Work Breakdown Structure (PWBS)). This system was implemented in the decades of 1960 and 1970 and during this period IHI had outstanding results, producing over 2000 ships.

On the year of 1970, in the US, the National Shipbuild Research Program (National Shipbuilding Research Program (NSRP)) was created. During that decade, in order to exchange information and to promote technological improvements, this entity established a connection between the US and Japanese shipbuilders. In 1979, as a result of this cooperation, a book of reference named "Outfitting Planned" based on the PWBS. During the following decade NSRP improved the procedures of PWBS and published a vast amount of literature related to integrated construction (which includes outfitting). During the 1990's several shipyards tried to improve the results obtained from the US-Japan shipbuilding joint venture and discovered several different new types of production methods.

In 1991, as previously mentioned, Thyssen Nordseewerke (TNSW) built the 1700 TEU container vessel that used the modular solution [5], for the piping system of the engine room and that triggered the need for an integrated construction approach in order to enable the assembly of the modular outfitting units without under space crashing and potential rework. This was the first time that this type of procedure was applied [8]. During the 2000's decade fully integrated steel and outfitting construction were developed.

2.2.2.2 Integrated Shipbuilding Process

Integrated construction means that each process can be divided into interim parts that might be

combined at an optimum stage of the construction process [9], which improves the construction rate and reduces the number of conflicts and rework processes.

Modular outfitting approach is an internal sub process of the integrated shipbuilding process, which is widely used by the most advanced shipyards. Figure 2.2 shows a modern shipyard layout and the integrated outfitting assembly workflow.




Figure 2-2: Integrated outfitting assembly

Altic [9]

Integrated construction relies on the organization according to PWBS method that consists in a method of breakdown of the entire ship construction process into smaller and interim sub-processes gathered by type of technology among similar systems. This breakdown into interim sub processes enables the disentangling of activities that can be performed in parallel, instead of being performed sequentially.

Another fundamental concept is zone-orientated design. According to the NSRP [10], the most important principle in zone orientated design is: "...that material which is first assigned by function (system) is reassigned geographically" to excel the workflow. This methodology aims to increase the productivity indexes by centralizing all the work force and resources of a certain technological group on the same facility zone and by managing in parallel multiple technological groups. This approach intends to decrease the distance between materials and working stations, hence, it removes wasted steps and generates an agile workflow and consequentially enhances the production indexes. It also reduces barriers between group management entities and workers, improving communication among and across work teams. It is crucial to mention that every process of integrated construction is classified according to a PWBS code that creates a set of references to identify and organize all the working processes and the manufactured pieces.

According to Society of Naval Architects and Marine Engineers (SNAME)'s ship production book [11] there are three different integrated shipbuilding sub processes:

- i. **Hull Block Construction Method (HBCM)**
- ii. **Zone Outfitting Method (ZOFM)**
- iii. **Zone Painting Method (ZPTM)**

The Hull Block Construction Method and the Zone Outfitting Method are the most relevant sub processes for the scope of this thesis.

The goal of HBCM is to divide the ship structure manufacturing process into optimum blocks. Optimum blocks are designed considering structural elements plus outfitting components plus painting.

These three sub processes will be executed independently from one another and the quality of the block optimization will depend on the effective coordination between these parallel sub processes. Each of these sub processes is subdivided into lower level processes, which are defined according to the similarity of components regarding volume, weight and shape. This likeliness is important because it will sharpen the assembly of parts/components into modularized units.

2.2.2.3 Types of Modular Outfitting

Rubesa [1] also describes several types of modularized outfitting according to their complexity and to the phasing of assembly stage within the shipbuilding process. Some modularized units might only contain simple pipes and will be assembled on a block, prior to erection; while others might be extremely complex and include heavy equipment or a pre-outfit structure, which will be erected alongside with the ship's blocks. Table 2.1 describes the characteristics of modular units according to the complexity of equipment.

Modules may also differ according to the phase in which they are fitted in the ship structures.

Rubesa [1] defines the following types of outfitting:

- **On-unit outfitting:** Inside workshop outfitting assembly before fitting on-board
- **On-block outfitting:** Fitting of outfitting units on a structural block before block erection
- **On-board outfitting:** Installation of outfitting units directly on the ship prior or posterior to ship launch
- **Final outfitting:** Final outfit installation and testing on board

Table 2-1: Modularized units according to their equipment complexity

UNIT COMPLEXITY	DESCRIPTION
Pipe Unit	Constituted only by pipes manufactured and sub assembled in workshops
Machinery Unit	Constituted by one or more electric or mechanical components of a system manufactured and sub assembled in workshops
System Unit	Components of entire electrical or mechanical sub system
Structural Unit	Structural berth for heavy equipment units
Structural Machinery Unit	Merges a structural unit with a system unit
Pre-Outlet Block	Large dimension and High complexity unit composed by several systems To be erected alongside with the other blocks

2.2.3 Modular Outfitting advantages compared to Traditional Outfitting

Baade and Rubesa [1] advocate that Modular Outfitting has several advantages compared to Traditional Outfitting, namely in what concerns:

- i. Workers productivity and efficiency increase**
- ii. Outfitting costs and Man-hours decrease**
- iii. Number of interface points within the labor force on-board decrease, which smothers the shipbuilding process**
- iv. Modules manufacturing process related costs decrease, along with the number of built units, due to the implementation of standardized modules**

Traditional outfitting requires fewer efforts in the early design stages but increases the costs on late construction stages (as a result of the number of Man-hours used) contrarily Modular outfitting requires more effort in early design stages but decreases the effort in construction late stages.

Rubesa [1] showed that modular outfitting reduces the costs and the amount of Man-hours, by demonstrating that "the labor costs on-board can be in average 3-5 times higher than the equivalent work done in the workshop or on platform".

In order to prepare the shipyard to deliver maximum added value of modular outfitting, activities must be planned and allocated to work stations in a specific way and resources distribution must be reallocated regarding the traditional outfitting settings.

Gomes Lopes [3] illustrates the difference of planning and resources allocation between traditional outfitting and modular outfitting depending on outfitting process phase, in two charts (figures 2.3 and 2.4).




Figure 2-3: Resources (line width scale) allocated to TO assembly

Gomes Lopes [3]




Figure 2-4: Resources (line width scale) allocated to MO assembly

Gomes Lopes [3]

Besides the positive points mentioned above, Baade [5] describes another advantage of modular outfitting is the capacity to simultaneously perform work on several systems in parallel, in a synchronized way.

An example of parallel work is the case where steel blocks near the engine room area are assembled at the same time as the outfitting modules to be fitted in those very same blocks.

Even though, modular outfitting has multiple advantages, according to Rubesa there are also some disadvantages, such as:

- Design freedom decrease due to the space constraints on ship's inner parts
- Inner space requirements increase
- Heavier outfitting structures (due to modules structures) than in traditional outfitting
- Precision requirements of detail engineering substantially increase to avoid rework

2.3 Systematic Layout Planning (SLP)

As mentioned in the introductory chapter, one of the questions to be addressed in this dissertation regards the necessary layout changes required by the implementation of modular outfitting processes *versus* the implementation of traditional outfitting.


To answer this question, the Muther systematic layout planning method [12] was selected as the layout arrangement tool to be handled.

R. Muther defines [12] Systematic Layout Planning as a layout design methodology that aims towards the facilitation of the manufacturing process.

When solving a layout problem, designers will face the following questions:

- “**WHAT**” is going to be made/produced? (Product/Material)
- “**HOW MUCH**” of each item is going to be manufactured? (Quantity/Volume)
- “**HOW**” is it going to be produced? (Routing/Process Sequence).
(At this step production guidelines are defined, concerning flow sheets, process sheets, equipment's lists and others)
- “**WITH WHAT**” is it going to be produced? (Supporting Services)
(This includes all the auxiliary equipment related to the main production system)
- “**WHEN**” will it be produced? (Time)
This step is deeply related with the scheduling of the production activity.

Layout design is a continuous adapting process according to existing resources and limitations. These five elements are the foundation of the PQRST key to unlock layout problems and are represented in figure 2.5.



Muther [12]

Figure 2-5: PQRST key to unlock layout problems

2.3.1 Phases of layout planning

There are three primordial principles that constitute the backbone of a layout:

- **Relationships** - indicating the strength of the connection between things
(Example: Relationship between steel shop and panel line)
- **Space** - indicating the physical dimensions of a thing
- **Adjustment** - optimizing arrangement to allow things to fit more properly

R. Muther [12] stated that layout designing encloses a sequence of overlapping stages called the “Four phases of Layout Planning” (figure 2.6).

- **Location of the area to be laid out** - Has the purpose of determining the area where to install the facilities described in the layout.
- **General Overall Layout** - Defines general arrangement. A general sketch is made, and a rough flow pattern is established. General size, relationship and configuration between areas are defined.
- **Detailed Layout Plan** - Defines the precise location of specific equipment and machinery units. The level of detail design has to incorporate technical drawings, which includes electrical drawings; heavy equipment berths drawings and calculations reports.
- **Installation** - Creates the installation plan, approves the plan and physically implements the plan.




Figure 2-6: The phases of systematic layout plan

Muther [12]

Muther [12] also stated that the phases of “pure” layout planning, are phase II and III.

Phase II and III follow a common pattern of five procedures that are listed in figure 2.7, inside the boxes located on the left side of each phase main box.

This common pattern of procedure is composed by the following five procedures:

- **Procedure I.** Inputs
- **Procedure II.** Flow of Materials & other relationships
- **Procedure III.** Space Required & Available
- **Procedure IV.** Modifications and Limitations
- **Procedure V.** Evaluation & Approval

The SLP analysis which will be developed on this study, only concerns overall layout selection therefore, it is mostly focused on phase II of SLP.




Figure 2-7: Stages of SLP

2.3.2 Layout Developments

To create and develop the layout, each of the SLP procedures must deliver specific outputs, as stated below:

- **Procedure I** - identification of the needed activities to be developed and the space requirements
- **Procedure II** - perception of the relationships between activities and material flows
- **Procedure III** – definition of spaces required to accommodate each activity and their relationship and interface;
- **Procedure IV** - adjustments that enable realist plan implementation or potential improvements
- **Procedure V** - final layout selection among several possible alternatives, taking in consideration added values and cost, that once approved closes phase II

Layout development tools are used to complete procedure II and III.

There are three fundamental tools that will enable a systematic data collection, a user-friendly representation of activities flows, activities and space relationships, and that will also support the decision-making process of selecting the best layout among the several alternatives generated.

These tools are: the Relationship Chart, the Flow/Activity Relationship Diagram and the Space Diagram.

2.3.2.1 Relationship Chart

This tool provides the basis for the Flow/Activity diagram and is also an input for the space relationship diagram.

The Relationship Chart plots the existing relationships between the existing activities in a production system. It rates the activities closeness in a scale from A to X (A, E, I, O, U and X), being A an absolutely necessary relationship and X a non-desirable relationship (figure 2.8).




Figure 2-8: Example of relationship chart

2.3.2.2 Space Relationship Diagram

This diagram provides a visual representation that combines activities relationship and work flows. This type of diagram uses standardized ANSI symbols to represent the sort of activity performed and to represent the relationship closeness. It consists in a representation of the activity relationships and flows, superimposed on the space layout.

This diagram is based upon the relationship chart and the flow activity diagram combined with the space requirements and availability. However, instead of using the ANSI symbols to represent an activity it uses a representation of the infrastructures by scale (each site will be represented according to its area) and intersects this new representation with the flow lines plotted in the flow relationship diagram (annex B).

In the dissertation's SLP study, the Relationship Chart and the Space Relationship Diagram are the most relevant outputs for layout selection.

2.3.3 Layout Selection and Readjustments

The space relationship diagram provides several alternative layouts that will be compared in order to select the best one.

According to Muther [12] the selection of a new layout has to be made upon the three methods:

- i. Factor analysis rating**
- ii. Advantages and disadvantages weigh**
- iii. Cost comparison**

Once the final layout is selected it must be rearranged to accommodate requirements of reality conditions.

It is to be noted that on this dissertation the questions concerning implementation of modular outfitting will address layout adjustment and layout selection processes.

2.3.3.1 Layout Selection and Readjustment - Factor analysis rating

The multiplicity of factors that can affect a layout makes its analysis a complex problem. In order to overcome this complexity, a process of problem breakdown, named Factor Analysis, was developed. Thus, as in every complex engineering problem, it follows the methodology of dividing the problem into several smaller problem units that can be more easily managed. According to Muther [12] "The Factor Analysis method follows the engineering concept of breaking down the problem into its elements and analyzing each one".

Factor Analysis methodology has the following steps:

- i. List of all the meaningful factors to determine the layout to be implemented**
- ii. Balance the relative weight of each of the previous mentioned factors**
- iii. Rate the alternative layouts against each factor in a sequential way**
- iv. Compare the total value of all the alternative designed layouts**

2.3.3.2 Layout Selection and Readjustment - Advantages versus disadvantages weigh

This method allows the designer to clearly expose some key factors that should be taken in consideration in the layout selection process.

The weight of the exposed advantages or disadvantages is rated according to a vowel and numerical code rating (table 2.2).

This rating supports the designer recommendation regarding the possible adjustments of the layout design.

Table 2-2: (Dis)Advantages letter and numerical coding

RATING CODE AND VALUES		
Vowel Coding	Description of the rate	Numerical Value
A	Almost Perfect – (Excellent)	4
E	Especially Good – (Very Good)	3
I	Important Results Obtained – (Good)	2
O	Ordinary Results Provided – (Fair)	1
U	Unimportant Results – (Poor)	0
X	Not Acceptable – (Not Satisfactory)	?

R.Muther [12]

2.3.3.3 Layout Selection and Readjustment - Cost Comparison

The estimation of the overall costs must be based on the largest possible amount of available data in order to allow an accurate cost analysis to base the layout selection decision.

Cost comparison between layout alternatives is made upon the following parameters:

- i. **Flow Index**
- ii. **Transport Work**
- iii. **Cost estimation of material handling**

Flow index consists on the analysis of the layout efficiency in terms of workflow.

As the workflow depends on the distances between work stations and the activities relationships, this parameter is defined by analyzing the existing distance between activity locations and by analyzing activities closeness. Thus, SLP outputs, such as space relationship diagram, are critical tools for this analysis.

Transport work is defined by Muther [12], "... as intensity (of flow) times distance...". When designing a layout, it is necessary to estimate the costs of material handling/transport.

At this stage several flow relations were already defined and therefore both the paths to be used and their length are already known. Thus, multiplying distance by a two-way trip it is possible to estimate with satisfactory accuracy the total length covered.

Cost estimation of the definitive material handling, according to the already mentioned author

[12], implies not only the detailed definition of the working stations and the carrying equipment, as well as its working cost, but also the decision on where to place the handling terminals and the calculation of the distances between the station to pick-up and the station set-down.

The selection layout decision should also take in consideration cost comparison and differences in added value provided by each of the alternative layouts.

2.4 Risk Management

Decision making process implies problem analysis that includes risk estimation. Risk response plans should be developed in order to manage the identified risks. To implement a new outfitting installation method in the production line of an existing shipyard, the risk of unmet expectations and its potential additional costs have to be accessed.

The management of the project should also be based on the identification and prioritization of the favorable factors that are key to obtain results according to its goals.

In the introductory chapter, one of the three formulated questions of the dissertation scope of work, concerned modular outfitting implementation risk management.

Guedes Soares [13], has defined risk as "... the expected value of the process consequences per unit of time" (translated from Portuguese).

The Project Management Body of Knowledge (2008 PMBOK) [14] states that: "Risk management is the systematic process of identifying, analyzing and responding to project risk. It includes maximizing the probability and consequences of positive events and minimizing the probability and consequence of adverse events to project objectives"

The **six risk management major processes** are defined as per PMBOOK [14,ch11]:

- i. **Risk Managing Planning** - selects the way to approach and plan the risk management activities for a project
- ii. **Risk Identification** - determines the type of risks that can affect a project and itemizes their characteristics
- iii. **Qualitative Risk analysis** - executes a qualitative analysis of risks and conditions to prioritize their implications on the project's goals.
- iv. **Quantitative Risk analysis** - measures the probability and consequences of risks and reckoning their effect for the project goals.
- v. **Risk Response Planning** - develops procedures and techniques to magnify opportunities and decrease threats to the project's goals
- vi. **Risk Monitoring and Control** - monitors residual risk, identifies new risk, executes risk reduction plans, and appraises their effectiveness during the project life cycle

Concerning **risk analysis**, Guedes Soares [13] stated that it is a method that aims to determine the existing risk associated with a given process or system. There are two related approaches to risk analysis: qualitative and quantitative. Both were defined above but due to the scope of this thesis, only the qualitative approach will be detailed.

One useful risk analysis tool is the **likelihood-impact table/matrix**. This matrix displays for each identified risk, a risk score based on the estimated risk impact and on the estimated risk likelihood. This risk score is obtained by the multiplication of the weighted value of impact factor by the weighted value of likelihood factor. These weighted values are displayed in a scale from 1 to 5.

The risk scores results are displayed in a Probability-Impact table and their magnitude is represented by a color code of a four colors sequential scale.

According to PMBOK [14], the risk response planning can be defined as “the process of developing options and determining actions to enhance opportunities and reduce threats to the project's objectives”. Thus, the purpose of risk response is to decide which strategies should be taken to contain threats (or increase opportunities).

The adopted **risk response strategies** are the following:

- i. **Avoidance** - this strategy involves the need to revise the project to eradicate the risk. Usually this strategy is used in risk with high impact and high likelihood.
- ii. **Transference** - this strategy implies the deviation of the risk to a third party. This does not eliminate the risk but shifts the responsibility. Transferring is used in risk with high impact and medium likelihood.
- iii. **Mitigation** - this strategy looks for the reduction of the consequences of an adverse risk to an acceptable limit. It is applied on risk with medium impact and medium/high likelihood.
- iv. **Acceptance** - this strategy is characterized by the recognition of low impact risk and therefore, it can be accepted in the project without adjustments. This strategy is used for low impact risks and for low and medium likelihood factors.

Having described the risk response strategies, the next step of risk management processes is the creation and implementation of risk monitoring and risk control plans. This step is not to be developed in this dissertation, although it could be developed in future studies.

To estimate the impact factors of the identified risks, Guedes Soares and Gomes Lopes [15] suggested a methodology. This methodology quantifies every identified risk in terms of:

- **Quality**
- **Cost**
- **Time**

These parameters are individually quantified in a **scale from 1 to 5**, in which “1” stands for reduced impact and “5” for high impact. Once every parameter is quantified, all the values concerning each risk are summed.

It is to be noted that the study to be performed in chapter 5 will be based upon the risk identification process, the risk qualitative analysis and the risk response planning.

Success Factors, according to Rockart and Bullen [16], are circumstances that lead to outcomes that guarantee favorable and prosperous performance for an individual, a group or an organization.

Critical Success Factors are the decisive factors in which it is crucial to obtain positive results, in order to achieve the established objectives and to achieve success.

In this dissertation, contiguous to the risk management analysis, a sub chapter of Critical Success Factors was developed for the construction of a vessel in a medium size shipyard.

3

3 Comparison between man hours using Traditional Outfitting and Modular Outfitting

Contents

3.1 Problem modeling	32
3.2 Analysis Methodology.....	32
3.3 Results and Analysis.....	44

This chapter develops and analyzes the differences in terms of effectiveness (Man-hours) between a traditional outfitting method and a modular outfitting method. This study only includes the parts of the ship's bilge system.

3.1 Problem Modeling

The scope of this chapter is to describe the comparison of effectiveness between traditional on-board outfitting method and the modular outfitting method, regarding **work load** expressed in number of **Man-hours**, allocated to the installing and fitting part of a bilge system composed by **multiple pipe sections, valves** and **pumps**. (figure 3.5 and figure 3.6)

The workload data of the system's section was obtained from the technical drawings provided by AES, regarding bilge system pipeline isometric and bilge system lines diagram.

The **Man-hours** used to assemble each **pipe section** depended on factors such as **dimension, shape, location** and **position inside of the ship**.

3.2 Analysis Methodology

This section will describe the methodology used for the study of the implementation of modular outfitting methodology to the bilge piping system.

In a vessel there are several piping systems with a multiplicity of different components. For the study purpose, due to this extensive number of systems and components, it was defined that the production analysis would only be applied to the **ship's bilge system**.

Modular outfitting can only be used in selected groups of the pipe system that for the purpose of the study will be called **modular outfitting zones**, as per section 3.2.1.

According to Rubesa [1], **Modular outfitting**, when compared to traditional on-board outfitting, can have a potential impact on the necessary assembly workload because as already mentioned in subsection 2.2.3, it can **reduce assembly time down to 3 to 5 times**.

In this study the pipe sections of bilge system, suitable for the modular outfitting method, were selected upfront according to predefined criteria described in 3.2.1.

Subsequently the Man-hours actually spent on the selected sections of the bilge system were collected on field, then they were computed for both traditional outfitting and modular outfitting and finally they were compared.

3.2.1 Selection of the bilge system zones for Modular Outfitting implementation

The focus of this selection aimed to identify the most complex assembly outfitting procedures, that are the most time consuming, for which the return of an increase of production efficiency could be translated into a decrease of the workload (expressed in Man-hours).

Two **complexity parameters** were empirically defined:

- Highest quantity of elements per unit of space (m³)
- Space availability for fitting an outfitting module

The first step of the selection was to identify on the bilge's system isometric drawing the areas with the highest density of elements. Three areas were pinpointed.

The second step was to verify in the digital model of the vessel's system, provided by AES, if these three areas were the denser in terms of elements and if the space available was enough to fit a module.

The third step was to confirm the parameters on-board.

Having these parameters in consideration, **3 zones** were selected as being suitable for modular outfitting implementation:

- **Zone 1**- Located inside the Engine Room (ER) adjacent to the engine room's aft bulkhead (frame 23)
- **Zone 2** - Located inside the ER adjacent to the engine room's forward bulkhead (frame 39/40)
- **Zone 3** - Located inside the Auxiliary Equipment Room 1 (AER1) forward to the engine room's forward bulkhead (frame 43)

The number of pipe sections in each Zone are displayed in table 3.1 and the specific section's properties are displayed in annex **A**.

Table 3-1: Defined zones for Modular Outfitting, number of sections and location

Zone	# of elements	Location
1	14	Engine Room (near engine room aft bulkhead; FR #23)
2	27	Engine Room (near engine room fwd bulkhead; FR #39/40)
3	19	Auxiliary Equipment Room 1 (FR #43)

Every system element identified was coded according to the Work Breakdown Structure (WBS) methodology (figure 3.1) **that defined 4 digit levels, where:**

- the 1st digit is related to the compartment of the ship where the elements are placed
- the 2nd digit is related to the zone of the ship's compartment Modular Outfitting Zone)
- the 3rd digit is related with the element number
- the 4th digit is related with the sub-element number




Figure 3-1: Example that illustrates the 4 levels of the WBS codification used

3.2.2 Calculation of outfitting assembly Man-hours

The calculation of the potential Man-hours gain of the bilge system assembly and fitting resulting from the comparison between modular outfitting and traditional outfitting required the assessment of the workload of both outfitting methods.

3.2.2.1 Traditional outfitting assembly Man-hours variables

The Man-hours values depend on four main factors:

- **Pipe Dimension**
- **Pipe Shape**
- **Equipment Installing**
- **Pipe Location (inside the ship's compartments)**

Pipe Dimension is its major determinant. Figure 3.2 represents these factors composition.




Figure 3-2: Traditional outfitting calculation variables

This study took in consideration the workload factors above described in figure 3.2 for piping elements and equipment.

Concerning **outfitting complexity estimation**, the lesser degree was defined as the one corresponding to the pipes with the smallest dimensions (Nominal Diameter (DN) and length), with the simplest shape (less curves and branches) and located in the widest final position.

This pipe typology was used as the minimal complexity assembly value that was computed with the complexity incremental factors of the other pipe typologies (dimensions, shape and pipe location factors) according to predefined weighting coefficients.

3.2.2.2 Calculation of traditional outfitting assembly man hours

Traditional Outfitting assembly Man-hours (Mh_{TO}) corresponds to the sum of the pipe section's assembly Man-hours calculated in function of the pipe section's dimensions, shape (defined by the number of existing curves and branches) (Mh_{pip}) and location, with the equipment fitting workload (Mh_{equip}), as showed in equation 3.1.

$$\mathbf{Mh_{TO} = Mh_{pip} + Mh_{equip}} \quad (3.1)$$

Where:

$$\mathbf{Mh_{pip} = (Mh_{cuv} + Mh_{brch} + Mh_{loc}) \cdot Length}$$

$$Mh_{cuv} = Mh_{ND} \cdot C_{cuv} \cdot n_{cuv}$$

$$Mh_{brch} = Mh_{ND} \cdot C_{brch} \cdot n_{brch}$$

$$Mh_{loc} = Mh_{ND} \cdot C_{loc} \cdot C_{CGT}$$

$$\mathbf{Mh_{equip} = Mh_{ND} \cdot C_{equip}}$$

$$C_{equip} = (C_{pumps} + C_{filters} + C_{valves})$$

Equation 3.1 was developed into the following equation.

$$Mh_{TO} = Mh_{ND} \cdot Length \cdot (C_{cuv} \cdot n_{cuv} + C_{brch} \cdot n_{brch} + C_{loc} \cdot C_{CGT}) + (C_{pumps} + C_{filters} + C_{valves})$$

Where:

C_{brch}	Branches coefficient	
C_{CGT}	Coefficient to convert CGT of tankers to CGT Ro-Ro vessels	
C_{cuv}	Curves coefficient	
$C_{filters}$	Filters coefficient	
C_{loc}	Man-hour according to specific pipe section location	(table 3.5)
C_{pumps}	Pumps coefficient	
C_{valves}	Valves coefficient	
Mh_{brch}	Man-hours in function of existence of branches	(equation 3.4)
Mh_{cuv}	Man-hours in function of pipe section shape curves	(equation 3.3)
Mh_{ND}	Man-hours as function of nominal diameter ND	(equation 3.2)
Mh_{equip}	Man-hours in function of number of equipment	(equation 3.6)
Mh_{loc}	Man-hours in function of section's location (inside the ship)	(equation 3.7)
Mh_{TO}	Man-hours per pipe section for Traditional Outfitting	
n_{brch}	Number of branches	
n_{cuv}	Number of Curves	

3.2.2.2.1 Traditional outfitting Man-hours pipe assembly as function of dimensions (ND)

The pipe section's length was directly obtained from the AES technical drawings.

The traditional outfitting Man-hours, as function of nominal diameter (Mh_{ND}), was calculated by using as a reference, the values defined by Butler [17] for schedule 40 straight pipes according to the ND values, displayed in table 3.2.

Butler obtained these values in a shipyard shop floor, and therefore this accountability of Man-hours corresponds to the sum of the Man-hours concerning pipe removal, pipe manufacturing and pipe assembly (exclusive for straight pipes).

Table 3-2: Straight pipe repairing Man-hours per meter [17]

Straight Pipes (Schedule 40)	
Nominal Diameter - mm (ND)	Man Hours / meter (Mh)
32	3.2
65	5.2
80	6.3
150	12.5

As those values were the result of the total of Mh regarding pipe removal, plus pipe manufacturing and pipe assembly, in order to calculate the traditional outfitting straight pipe assembly Man Hours (Mh_{ND}) it was necessary to subtract the Mh used in pipe manufacturing (Mh_{manuf}) from the Mh used in pipe repair (Mh_{repair}) and to divide this difference by two, because it was assumed that the amount of Mh

for pipe removal is equal to the amount of Mh used for pipe assembly.

This ratio is expressed in the following equation (eq. 3.2) that enables the calculation of the straight pipe assembly Man-hours, for each Nominal Diameter.

$$Mh_{ND} = \frac{(Mh_{repair} - Mh_{manuf})}{2} \quad (3.2)$$

Mh_{ND} - Assembly Man-hours from equation 3.2

Mh_{Repair} - Ship repair Man-hours, according to table 3.2

Mh_{manuf} – Manufacturing time for each pipe section from equation 3.10

3.2.2.2.2 Traditional outfitting Man-hours in pipe assembly as function of shape

As mentioned before, the shape of the pipes, defined by the curves and branches, is one of the factors that influence the number of used Man-hours.

In order to calculate the terms Mh_{cuv} and Mh_{brch} , of the equation 3.1, that correspond to the influence of section curves and branches on Man-hours increase, it was necessary to compute a standard number of Man-hours defined by Butler [17], with the number of curves and branches weight by coefficients, as per equation 3.3 and equation 3.4.

$$Mh_{cuv} = Mh_{ND} \cdot C_{cuv} \cdot n_{cuv} \quad (3.3)$$

Mh_{cuv} - Pipe section's assembly Man-hours increase due to section curves

Mh_{ND} - Assembly Man-hours as function of ND

C_{cuv} - Curves coefficient

n_{cuv} - Number of curves

$$Mh_{brch} = Mh_{ND} \cdot C_{brch} \cdot n_{brch} \quad (3.4)$$

Mh_{brch} - Pipe section's assembly Man-hours increase due to branches existence

Mh_{ND} - Assembly Man-hours as function of ND

C_{brch} - Branches coefficient

n_{brch} - Number of branches

The pipe's curves and branches coefficients were empirically defined according to the output provided by Professor Gomes Lopes based on his expertise and experience as a production director in LISNAVE shipyards (table 3.3).

Table 3-3: Pipe's Curves and Branches coefficients

C_{cuv}	0.05
C_{brch}	0.20

3.2.2.2.3 Traditional outfitting man hours for equipment installing

The accounted equipment includes pumps, valves and filters.

To calculate Mh_{equip} , it was used the Man-hours computed by equation 3.2 and a equipment installing coefficient C_{equip} .

The influence of equipment Mh_{equip} installing is computed by equation 3.5:

$$Mh_{equip} = Mh_{ND} \cdot C_{equip} = Mh_{ND} \cdot (C_{pumps} + C_{filters} + C_{valves}) \quad (3.5)$$

Where:

Mh_{ND} - Assembly Man-hours as function of ND (equation 3.2)

C_{equip} - Equipment installing coefficient

C_{valve} - Valve installing coefficient

$C_{filters}$ - Filter installing coefficient

C_{pumps} - Pump installing coefficient

Pumps and filters coefficients have a bigger value when compared to valve coefficient due to the higher complexity of the installing of pumps and filters. Installing valves as a lower workload because of the previous installation of spool pieces.

The equipment coefficient was empirically defined by Gomes Lopes (table 3.4) as per the shape coefficients.

Table 3-4: Equipment installing coefficient

C_{pumps}	1.2
$C_{filters}$	1.2
C_{valve}	0.80

The values from table 3.4 hold in account the fitting of the equipment inside the vessel. As stated in the introduction chapter, the equipment was placed inside the ship before the erection of the block that encloses the compartment where equipment is to be fitted. Therefore, the equipment coefficient includes both the workload necessary to carry them from the previous location where they were placed and the fitting workload.

3.2.2.2.4 Traditional outfitting man hours in pipe assembly as function of location

The impact in the number of Man-hours spent for pipe assembling, depending on the location of the pipes inside the ship (Mh_{loc}), is given by the equation 3.6 that is a term of the main equation 3.1.

$$Mh_{loc} = Mh_{ND} \cdot C_{loc} \cdot C_{CGT} \quad (3.6)$$

Mh_{loc} - Man-hours according to section's location (inside the ship)

Mh_{ND} - Man-hours as function of ND

C_{loc} - Man-hour according to specific pipe section location, table 3.5 [17]

C_{CGT} - coefficient to convert CGT of tankers to CGT Ro-Ro vessels (equation 3.6)

To calculate the values of Man-hours depending on pipe location, it was used the values of coefficient

(C_{loc}) stated in the literature for tanker ships [17] together with a conversion coefficient (C_{CGT}) that had to be determined with the purpose of adapting the tanker ship coefficients C_{loc} to the ferry ship specifications.

Table 3.5 [17] displays the value of tanker’s C_{loc} (Man-hours according to location) depending on the specific pipe position (double bottom, holds and tanks, aux and engine room).

As the Ro-Ro Haksolok does not have a pump room (typical from tanker ships), but instead, she has three auxiliary equipment rooms, it was assumed the same C_{loc} value of the tanker pump room, for each of the three auxiliary rooms: Auxiliary Equipment Room 1 (AER1), Auxiliary Equipment Room 2 (AER2) and Auxiliary Equipment Room 3 (AER3).

Table 3-5: Value of C_{loc} depending on specific pipe position for a tanker ship [17]

Pipe Position	Additional charges
Double bottom	30%
Hold and ballast	30%
Aux Equip. Room 1	30%
Aux Equip. Room 2	30%
Aux Equip. Room 3	30%
Engine Room	40%

As previously mentioned, the C_{loc} values from table 3.5 concern tanker ships and had to be converted to be used in a ferry/Ro-Ro vessel.

This conversion was based on the ratios between the values of CGT of tanker type vessels and the value of CGT of Ro-Ro and that implied the previous calculation of CGT for each of the two types of vessels.

OECD developed an indicator designated compensated gross tonnage (CGT) in order to compare the cost of vessels or the outputs of shipyard manufacturing.

This indicator is calculated by equation 3.7:

$$CGT = A \cdot GT^B \tag{3.7}$$

- A - A factor represents the influence of ship type
- B - B factor represents the influence of ship size
- GT - corresponds to gross tonnage

OECD has derived these factors through an Ordinary Least Squares (OLS) regression from a substantial sampling of shipyards outputs and has then provided values for both A and B factors by ship type segmentation, as listed in table 3.6.

Table 3-6: OECD A and B factors (coefficients) of influence per ship type and per ship size [18]

Ship type	Oil tankers (double hull)	Oil tankers (double hull)	Chemical tankers	Bulk carriers	Combined carriers	General cargo ships	Reefers	Full container	Ro ro vessels	Car carriers	LPG carriers	Ferries	Passenger ships	Fishing vessels	NCCV
A	48	84	29	33	27	27	19	32	15	62	32	20	49	24	46
B	0,5	0,5	0,6	0,6	0,6	0,6	0,6	0,6	0,7	0,5	0,6	0,7	0,6	0,7	0,6
	7	5	1	2	4	8	8	3	0	7	8	1	7	1	2

To obtain the value of the coefficient to convert the C_{loc} of tankers to the C_{loc} of Ro-RO Haksolok, it was used the ratios between the values of CGT of tanker type vessels and the value of Ro-Ro CGT (equation 3.8).

$$C_{CGT} = \frac{CGT_{tanker}}{CGT_{RoRo}} \quad (3.8)$$

CGT_{tanker} - CGT of a tanker type vessel
 CGT_{RoRo} - CGT of a Ro-Ro type vessel

To calculate CGT for each of the two types of vessels mentioned above, the OECD equation 3.8 was used as well as the values of A factor and B factors predefined in table 3.6 according to ship type.

In what concerns the gross tonnage (GT) value: the one of the Ro-Ro Haksolok was kindly provided by AES, but the GT of the tanker ships had to be computed, because it was not directly available from the literature.

This computation the GT of the tanker ships had to be based on DWT values.

Bearing in mind that C_{loc} values for tankers provided by Butler [17] were based on data collected during the repair of tanker vessels in the year of 1999, it was assumed that the gathering of tanker repair data should have been derived from most of the existing worldwide repaired tanker fleet in 1999. Fearnleys 2000 annual review [19] compiled existing data concerning 1999 worldwide repaired tanker fleet, displayed in function of the vessel's DWT. (table 3.7)

However, Fearnleys DWT data concerning the tanker fleet was displayed in ship's DWT intervals. For that reason, in order to obtain a sole DWT value for tanker ships, it was necessary to compute the weighted arithmetic average fleet DWT and to use this medium value as the intended GT value.

After determining the weighted arithmetic average value, it was then possible to use it as an estimation of the GT of the worldwide tanker fleet in 1999.

Table 3-7: 1999 DWT shipped by the worldwide tanker fleet segmented by ship's DWT

Vessel's DWT intervals (1000 of tons)	10-25	25-40	40-50	50-80	80-120	120-200	200-320	320
Vessel's DWT intervals average (1000 of tons)	17.5	32.5	45	65	100	160	260	320
Carried DWT (1000000 of tons)	6.3	19.7	12.3	18.4	49.3	41.6	103.4	21.7

Once this tanker GT value was calculated, the next step was to obtain the corresponding CGT value. So as to, the marine traffic website was searched to identify a tanker with a DWT value near to the tanker arithmetic average DWT in order to obtain a GT value that could be used as the intended tanker CGT value. Once both the values of CGT for Ro-Ro Haksolok and for tankers ships were computed, it was then possible to calculate the ratio between them, and to determine the value of the coefficient to convert the *Cloc* of tankers to the *Cloc* of Ro-RO Haksolok. (results in table 3.9)

3.2.2.2.5 Calculation of traditional outfitting manufacturing Man-hours

Butler [17] states that the pipe section shape and pipe section length are factors that increase the number of manufacturing Man-hours (Mh_{manuf}), and for that reason this had to be taken in consideration for the Man-hours calculations.

The following equation was developed

$$Mh_{manuf} = Mh_{ND_{Manuf}}(1 + C_{brch} \cdot n_{brch} + C_{cuv} \cdot n_{cuv}) \quad (3.9)$$

$Mh_{ND_{manuf}}$ - Unitary Mh straight pipe manufacturing from table 3.8

C_{cu} - Shape coefficient

n_{cu} - Number of curves

C_{brch} - Branches coefficient

n_{brch} - Number of branches

The number of Man-hours used in pipe fabrication depends linearly on the pipe length (table 3.8) but also depends of ND and on the pipe shape (to calculate the manufacturing time increase due to shape, the coefficients from 3.2.2.2 were used).

Table 3-8: Unitary straight pipe manufacturing Man-hours [20]

ND (mm)	Mh/m
32	0.11
65	0.13
80	0.13
150	0.17

The values of Man-hours used in pipe repair (table 3.2) also depend on the size of pipe's nominal diameter.

An important point is the fact that the values of pipe manufacturing increase linearly alongside with pipe length. Therefore, it can be said that dimension variation will affect the number of Man-hours.

3.2.2.3 Modular Outfitting Man-hours calculation

The calculation of the number of Man-hours used on installing, assembly and fitting of a modular outfitting process was based on the calculations that were made for traditional outfitting.

The modular outfitting to be implemented, implies that the assembly of the modules is to be carried inside the outfitting shops and subsequently the fitting of the modules in the block is to be carried in a phase prior to on-ramp block erection (modules fitted in the block manufacturing park).

As already stated and according to Rubesa [1], the value of assembly Man-hours associated to modular outfitting can be between 3 to 5 times smaller than the value of assembly time related with traditional outfitting, or numerical expressed it represents respectively 0.3 (3) to 0.2.

Based on this reduction, it was assumed that the assembly Man-hours on shop would decrease linearly with the Man-hours in function of the pipe sections complexity.

In traditional outfitting it takes more time to assemble pipes with larger dimension and several shapes (arising from the limitations to insertion, positioning and assembly in the on-board confined spaces) than to assemble simpler pipes. Thus, if there is the possibility of assembling the more complex pipes on a wider outside space it can be assumed that the **reduction value of Man-hours in modular outfitting** would be of greater magnitude in more complex pipe sections than in simpler pipe sections. For this reason, it was assumed that the highest **value of Man-hours reduction of 0.2** would correspond to the Man-hours decrease of more complex sections and that the **lowest value Man-hours reduction of 0.3(3)** would correspond to the Man-hours decrease of simpler sections.

The following factors were considered to define the pipe sections assembly Man-hours:

- section's curves
- section's number of branches
- section's length
- section's equipment (if any)

Data has been collected for each pipe section from the bilge system isometric drawings. This has enabled the calculation of a complexity score for each pipe section based on the sum of the partial complexity values of the pipe section's regarding curves, branches, length and installation of equipment relatively to the maximum possible value that each of these factors can assume.

Each of the factors are designated as:

f_{cu} - (curves factor) equation 3.10

f_{brch} - (branches factor) equation 3.11

f_{length} - (length factor) equation 3.12

f_{equip} - (equipment factor) equation 3.13

$$f_{cuv} = \frac{n_{cuv}}{\max n_{cuv}} \quad (3.10)$$

$$f_{brch} = \frac{n_{brch}}{\max n_{brch}} \quad (3.11)$$

$$f_{length} = \frac{length}{\max length} \quad (3.12)$$

$$f_{equip} = \frac{n_{equip}}{\max n_{equip}} \quad (3.13)$$

n_{cu} - number of section's curves

n_{brch} - number of section's branches

n_{length} - section's length

n_{equip} - number of section's equipment

$\max n_{cuv}$ maximum number curves of all pipe sections

$\max n_{brch}$ - maximum number branches of all pipe sections

$\max n_{length}$ - maximum length of all pipe sections

$\max n_{equip}$ - number of section's equipment

The value of the complexity score, designated as pipe section's "f" factor(f) score, is calculated as the sum of the values of the four above mentioned factors, equation 3.14.

$$f = f_{cuv} + f_{brch} + f_{length} + f_{equip} \quad (3.14)$$

Once each pipe segment's f was calculated, the corresponding Man-hours reduction rate R_{Mh} was computed by linear interpolation, equation 3.15

$$R_{Mh} = R_{Mh_1} + \frac{R_{Mh_2} - R_{Mh_1}}{f_2 - f_1} \cdot (f_2 - f_1) \quad (3.15)$$

In which:

- R_{Mh_1} and R_{Mh_2} are the value immediately above and below the section's R_{Mh} value
- f_2 and f_1 are the value immediately above and below the section's f value

Having calculated each pipe section's man-hour reduction factor R_{Mh} , the pipe section's modular outfitting assembly Man-hours could be computed by equation 3.16.

$$Mh_{MO} = R_{Mh} \cdot Mh_{TO} \quad (3.16)$$

Once every pipe section's modular outfitting Man-hours assembly value was calculated, a sum of all section's Man-hours was obtained in order to enable its comparison with the sum of the total traditional outfitting pipe section's assembly Man-hours, as per equation 3.17.

$$\Delta Mh = M h_{TO} - M h_{MO} \quad (3.17)$$

3.3 Results and Analysis

As defined in section 3.2.1, the following three suitable bilge system zones for implementing modular outfitting (table 3.1) and to analyze the Man-hours difference between the two outfitting methods (traditional outfitting *versus* modular outfitting) were selected:

1. **Engine Room** (near engine room aft bulkhead)
2. **Engine Room** (near engine room fwd bulkhead)
3. **Auxiliary Equipment Room 1**

Before presenting the results concerning modular outfitting Man-hours assembly calculation it is important to specify two intermediate calculation steps concerning CGT ratio (C_{CGT}) and concerning the correspondence between the f value and reduction rate R_{Mh} .

The coefficient C_{CGT} corresponds to the ratio between the Haksolok CGT and a tanker CGT. The tanker CGT was computed from the GT of the tanker vessel "Li Chi" with a DWT similar to the weighted arithmetic average DWT value of the 1999 tanker fleet.

The Haksolok CGT was computed through equation 3.8 from its actual GT value.

Table 3.9 displays the CGT ratio parameters.

Table 3-9: CGT tanker and Ro-Ro values

Vessels	DWT	GT	CGT	RATIO*
Tanker "Li Chi"	48.653	30.325	-	-
1999 Tanker Fleet weighted arithmetic average	47.914	30.000*	17.108	4,32
Ferry/Ro – Ro "Haksolok"	-	2.095	3.958	

* estimated from the "Li Chi" GT based on DWT similarity

As previously stated, the calculations of the reduction in Man-hours from traditional outfitting to modular outfitting implementation were based on the correspondence between pipe section (f factor) and Man-hours reduction rates defined on the literature [1].

f factor score was calculated for every pipe element, as per the above methodology, and then it was possible to define the complexity score range which contained all the values, within a range in which the maximum value corresponds to 3.1 and a minimum value to 0.

Considering that on the transition from traditional outfitting to modular outfitting, complex pipes assembly time would lead to a greater improvement than simple pipe assembly times, it was empirically defined that a section with $f=3.1$ would lead to a five times decrease [1] and that a section with $f=0$ would lead to a three times decrease [1]. This translates into a Mh reduction rate of 0.3(3) for the complexity value of 0 and a reduction rate of 0.2 to a complexity rate of 3.1 (table 3.10).

Table 3-10: MO versus TO - Man-hours (Mh) reduction

Complexity score (f)	MO vs TO - Mh reduction rate
0	0.3(3)
3.1	0.2

Then, using a trend line (linear interpolation), it was computed the Mh reduction factors for intermediate f values. These intermediate values were then used in the calculations of the Man-hours difference between traditional outfitting and modular outfitting assembly methods for each one the pipe sections.

Once these intermediate calculation steps were specified, the results concerning modular outfitting Man-hours assembly were computed.

The pipe section’s assembly Man-hours values for both traditional outfitting and modular outfitting, for every analyzed pipe sections, are displayed in annex A.1 and are represented in figures 3.4.and 3.5.

Specific colours of bars were used for each one of the outfitting methods results:

- blue bar - for traditional outfitting method
- red bar - for modular outfitting method

When comparing the difference in assembly Man-hours between traditional outfitting method and modular outfitting method, and in line with the assumption of the Man-hours reduction according to pipe section complexity, it was possible to observe that in general the more the pipe sections were complex, the greater was the magnitude of Man-hours reduction.

The four most complex and the four simplest pipe sections are described in table 3.11.

Table 3.11 shows the values obtained from equation 3.17. The properties of the four most complex pipe sections and four least complex pipe sections of the bilge system are displayed in table 3.11.

The order of magnitude of Man-hours difference, designated as “Difference”, calculated by equation 3.17 is displayed in the last column of the already mentioned table 3.11.

The results in this column clearly show that the four most complex pipe sections have a more significant man-hours difference than the four simplest pipe sections, when comparing traditional outfitting and modular outfitting.

Table 3-11: More complex and least complex Pipe sections description

WBS	Yard code	ND (mm)	Length (m)	Curves	Branch	Valves	Pumps& Filters	TO Total Mh	MO Total Mh	diff**
1.2.3.1*	041005	80	4.41	3	2	0	2	37.38	7.48	29.90
1.1.6.2*	031002	80	4.03	0	0	0	0	28.10	7.82	20.27
2.3.7.1*	105001	80	2.48	4	0	0	0	27.84	7.46	20.38
2.3.2.2*	041011	80	2.33	7	0	1	0	27.60	6.40	21.20
1.2.8.1*	009001	32	0.53	1	0	0	0	4.53	1.43	3.10
1.2.11.2*	003001	32	0.52	1	0	0	0	4.49	1.42	3.07
1.2.8.2*	009001	32	0.31	1	0	1	0	3.89	1.13	2.77
1.1.2.2*	013001	32	0.22	1	0	1	1	3.64	0.97	2.68

*More complex pipe sections; *Less complex pipe sections; ** Pipe section difference in Mh between TO and MO

The pipe section that spent the largest amount of Mh to be assembled, according to the defined work breakdown structure, was section 2.8.1. This section took 37.38 Mh to be assembled by a traditional outfitting method and 7.48 Mh to be assembled by a modular outfitting method, therefore, there is a difference of 29.90 Mh.

Analyzing the simplest section to be fit, section 2.6.2, it is possible to verify that the different between the outfitting methods is quite smaller, and that this difference equals 3.10 Mh.

Table 3.12 and figure 3.3 displays the results regarding the total difference between Man-hours used in the traditional outfitting process and the used Man-hours in the modular outfitting (on-block) approach for the selected parts of the bilge system computed according to equation 3.17. The raw values used in the sum are displayed in table A.1 (Annex A).

In figure 3.3, trendlines were computed for both curves. It is possible to observe that the trendlines functions of each curve do not intercept on the positive domain ($f_1 \neq f_2, if x \in \mathbb{R}^+$).

One of the trendlines function characteristics that must be outlined is that both trendline functions diverges when the abscissa approaches infinity. This means that if the amount of pipe sections to be assembled and fitted increases, the difference between traditional outfitting trendline and modular outfitting trendline will also increase.




Figure 3-3: Man-hours used for pipe assembly process by TO or MO

Table 3-12: Summed results of MO and TO assembly Mh

Total Results	Mh
Sum of Traditional on-board Outfitting	781.67
Sum Modular on-block outfitting	202.87
Difference between TO and MO	548.80

For the three selected sections of the bilge system it can be observed that by using a modular outfitting approach, about 26% of the assembling man hours used in the traditional outfitting method will be spend, which in numerical terms, represents a decrease 548.80 Mh (a reduction of 74% of the workload).

Outfitting (modular) in integrated construction implies a design workload increase when compared with non-integrated shipbuilding processes. In this study the designing workload was not included in the displayed results.

Module structure manufacturing and welding to the fitting birth was also not held account in the bilge system modular outfitting work flow computations.

Although both these elements were not considered in modular outfitting workload assessment, it can be assumed that due to the large difference between both outfitting methods, modular outfitting would still represent a work flow decrease when compared to traditional outfitting.

This total difference of 548.80 Mh results from the analysis performed on the scope of this study that concerns only of part of a single piping system (bilge system), although it can be applied to all the piping systems and other outfitting systems.

A ferry vessel such as the “Haksolok” contains numerous piping systems that have more and heavier pipe sections than the bilge system. Therefore, it possible to extrapolate that the difference of both outfitting methods would increase.

Hence, it is valid to extrapolate that modular outfitting implementation could represent a significant decrease on the vessel’s outfitting workflow.

Figure 3.5 shows an example of the module to be implemented in modular outfitting zone number 1.

Figures 3.6 show the location inside the ship where the modular outfitting zone 1 module is to be fitted.




Figure 3-4: Man-hours used for the assembly of each pipe section by TO or MO (part1)




Figure 3.4: Man-hours used for the assembly of each pipe section by TO or MO (part 2)




Figure 3-5: Modular outfitting zone number 1




Figure 3-6: Modular outfitting zone number 1, 3D model and Modular outfitting zone number 1, on site photo

4

4 Systematic Layout Planning for Modular Outfitting

Contents

4.1 Problem Modeling	54
4.2 Methodology	54
4.3 Shipyard's layout changes and results.....	56

This chapter analyses the necessary changes in layout towards modular outfitting production optimization. The main concern of this study was the location of the shops to be used for modular outfitting assembly, in the existing shipyard (Atlantic Eagle Shipbuilding yard). Richard Muther's Systematic Layout Planning [12] was the chosen method to develop this analysis.

4.1 Problem Modeling

This Systematic Layout Planning analysis was made from a shipbuilding process perspective (instead of ship repair process) using modular outfitting.

Considering the needs of modular outfitting units' construction, it was assumed that a new dedicated outfitting shop would be necessary. Therefore, three questions were formulated:

- i. Where should the outfitting shop be located?**
- ii. What implications would it have on upgrading costs for the existing buildings/shops?**
- iii. What impact would it have on the flows of other shipyard's processes?**

Examining each question in detail and starting with the first question, the biggest problem was the viability in terms of materials flow.

- i. Due to its high cost, the constructing of a new building shop was out of the question therefore; the implementation of a new outfitting shop should be on an existing facility. For the flow related reasons, this new shop should be as close as possible to the block assembly park, however it would important that the selected building would have the needed dimensions for the designated activity.
- ii. In what concerns the second question, there was a need to avoid significant added costs related to building's reworks.
- iii. Regarding the third question, the following described constrains were identified. The first constrain was that any change to the allocation of activities of the selected buildings should have a minimal impact on the rest of the other processes in the shipyard. The second constrain was that the shift of materials and equipment inherent the reallocation of function of the existing buildings, should not add significant costs.

4.2 Methodology

The methodology implemented according to the process, represented in Figure 4.1 and described below, was applied to answer the questions defined in section 4.1.

There are several methodologies for facility planning, namely: the Systematic Layout Planning methodology (SLP), the Graph Based Theory (GBT), Dimensionless Block Diagram (DBD), among others.

From this range of possible facility planning methodologies, SLP was selected, because of its perceived advantages. SLP is an intuitive and easy learning technique with reliable results. Also, it has a vast

amount of available and thrust wordy information (articles, books and reports from real life facility implantations). In what respects the CAD software Autocad, it exists an SLP related add-in (*Proplanner*) which was very useful for the development of the layout analysis inherit to this dissertation.

In order to develop the layout study, it was necessary to collect data concerning paths of materials and equipment and also concerning the average amount of time spent in each trip between buildings used in traditional outfitting, so that the average time spent by the mobile equipment while transporting the loads through the circuits defined for pipe assembly process could be estimated. (Figure 4.1).

Another piece of data that was crucial to this study was the technical layout drawing of the shipyard's scaled layout. The drawing of the AES shipyard layout that was supplied for the purpose of this study, provided the information regarding the distances between shops and buildings.



Figure 4-1: Layout study process

After data collection, it was possible not only to project the layout changes that would optimize the time and space efficiency of the modular outfitting implementation, but also to compare the traveling times between the existing layout configurations with the modular outfitting suggested layout.

A specific flow software was used for the new layout design purpose (Flow Planner an AutoCAD add-in) and this software provided two types of layout outputs:

- i. First type concerns the Systematic Layout Planning Theory (mentioned in subsection 2.3.2) and its two most important outputs were the **Relationship Chart** and the **Space Relationship Diagram**, which are produced in the overall layout phase.
- ii. Second type of output concerns the needed changes in the **Material Flow Routes** (distance and time) resulting from the suggested modular outfitting adapted layout (see tables 4.5 and 4.4). It was necessary to produce sketches for both types of outputs.

The shipyard general arrangement layout drawing (for the existing traditional outfitting layout) provided by AES did not include the previously defined Flow/Activity Diagrams or closeness relationship rates.

For this reason it was necessary to create this diagram and to define the relationship rates for both the existing traditional outfitting layout and the new suggested modular outfitting layout. The traveling time and the trip distances between shops outputs associated with the changes in routes were presented as tables of results (tables 4.4 and 4.5). For both traditional outfitting and modular outfitting layouts, the time and the distance between the routes of the shops/buildings, were calculated and subsequently compared (tables 4.4 and 4.5).

4.3 Shipyard's layout changes and results

4.3.1 Factor analysis

Following the theory stated in subsection 2.3.3.B, in order to comply with the readjusting layout methods, it was necessary to breakdown the main layout readjusting problems.

When readjusting the layout to adapt it to the needs of the modular outfitting construction processes, the matters in the three questions formulated in 4.1 had to be addressed, namely in what concerns: the outfitting shop closeness to the block assembly, the park and the impact of activities reallocation on building's reworks costs and on material's flows.

To implement the traditional outfitting layout and to simultaneously answer the three questions formulated, the changes should be as follows:

- i. **Change no. 1** - Plasma cutting machine should be moved to a new location near the steel shop
- ii. **Change no. 2** - New outfitting shop should be placed into contiguous: to where the plasma cutting machine used to be and the other where the old outfitting shop was
- iii. **Change no. 3** - Park to storage plates and steel profiles should be created near the plasma-cutting machine

The suggested changes were based on the following rationales:

- i. Change no. 1 aimed to decrease the distance between the cutting and steel shop and therefore, to have a positive influence on the block manufacturing efficiency
- ii. Change no. 2 was due to the fact that the place where the cutting machine used to be, was the one that better fit in terms of flow analysis for the new outfitting shop, because this shop is closer to the path that goes to the block assembly park
- iii. Change no.3 is due to the fact that change 1 has relocated the cutting machine near the steel shop that is further away from the reception park. There is a wide space near the new location of the cutting machine that could be reorganized to accommodate a closer steel storage park without significantly harming other production processes

As there were no available preexisting buildings near the steel shop area, change no. 1 would imply the need for an extra building. In order to avoid high expenses, this building should be a pre-fabricated building that could be either acquired or rented. The alternative of a pre-fabricated building would potential reduce the costs of change no. 1, comparatively to the construction of a new building.

4.3.2 Layout changes - Advantages versus Disadvantages

Following the procedures mentioned in 2.3.3, the advantages and disadvantages of the layout changes were weighed and rated.

For change no 1 (plasma cutting machine) and change no 2 (new outfitting shop), the advantages and disadvantages were listed and rated in accordance to the code exposed in table 2.2 and the results were compiled in tables 4.1, 4.2.

Table 4-1: Advantages vs disadvantages analysis for the changing of the cutting machine position

Cutting machine position						
Existing Layout			Suggested Layout			
	Item	Rating		Item	Rating	
ADVANTAGE	1	Shop with larger dimensions	O	1	Closer to the steel shop	A
	2	More space to store and organize the pieces and plates to be cut	I	2	Closer to the prefabrication shop	A
	3	Closer to yard repair ramp	E	3	Closer to block assembly park	E
DISADVANTAGE	1	Further away from steel shop	A	1	Further away from ship repair ramp	E
	2	Further away from pre-fabrication shop	A	2	Additional cost due to the need of a new building	A
	3	Further away from block manufacturing park	E	3	Adds costs for moving the shop's equipment towards the new location	I

Table 4-2: Advantages vs disadvantages analysis of the new outfitting shop

New Outfitting Shop						
Existing Layout			Suggested Layout			
	Item	Rating		Item	Rating	
ADVANTAGE	1	Does not add costs of moving the shop's equipment towards the new location	I	1	More space to assemble piping units	A
	2			2	Creates a hub point to all piping related processes	A
DISADVANTAGE	1	Does not have enough space for assembling modular outfitting units in a single shop	A	1	Adds costs for moving the shop's equipment towards the new location	I

For the change no 3 (steel storage park relocation) no disadvantages were identified and so there was no need to weighed against advantages. The two advantages identified were:

- Closeness of the steel storage park to the new location of the cutting machine reduces the traveling time
- No dislodgement of any activity or equipment because the park relocation was in an empty area and so no added costs are expected.

To numerically weigh the advantages against the disadvantages, the numerical factors associated with the letter rating [12] were used. The numerical factors were within a range of zero to four, where zero is represented by the letter "U" and four by the letter "A".

Summing the numerical factor of each advantages/disadvantage (equation 4.1) the final weighed results of the advocated layout changes were obtained and exposed on table 4.3.

$$Weight_{ADVvsDES} = \sum_{i=1}^n Rating_i - \sum_{j=1}^n Rating_j \quad (4.1)$$

Table 4-3: MO/TO advantages against disadvantages weigh

		Advantages (i)	Disadvantages (j)	Difference (Eq. 4.1)
Cutting Machine Position	Suggested Layout	11	9	2
	Existing Layout	6	11	-5
Wider Outfitting Shops	Suggested Layout	8	2	6
	Existing Layout	2	4	-2

The **major advantages** of the existing **traditional outfitting** layout are:

- Existence of a large workshop for steel cutting processes
- Location of the steel cutting workshop nearby the repair ramp

The **major disadvantages** of the existing **traditional outfitting** layout are:

- Location of the cutting machine far away from steel shop location
- Location of the cutting machine far away from panel line shop location
- Location of the cutting machine far away from block manufacturing park location

The **major advantages** of the suggested **modular outfitting** layout are:

- Location of cutting machine nearby steel shop, panel line and block manufacturing park
- Existence of larger outfitting workshops
- Existence of a hub point for all outfitting related processes
- Closeness of the steel storage park to the new location of the cutting machine

The **major disadvantages** of the suggested **modular outfitting** layout are:

- Cutting machine further away from repair ramp
- Existence of added costs due to the renting/acquiring of a pre-fabricated building.

In terms of result discussion, the already existing traditional outfitting layout, had an overall non-positive result when compared with the new suggested layout. This previous layout, as mentioned in table 4.2, has some disadvantages that were associated with the order of magnitude of the distance between the location of the cutting machine and the location of the steel shop and panel line.

Focusing now on the outfitting shops, the major disadvantages of the existing traditional outfitting layout are related to the potential lack of space for the implementation of modular units assembly processes. On the other hand, this layout has the advantage of being located nearby the ship repair ramp.

Regarding the new suggested modular outfitting layout, the overall results were positive (table 4.3). For all the proposed changes, most of the disadvantages are linked with the costs of equipment

repositioning process and of infrastructure.

As advocated before, the transference of the cutting machine towards a new location, would imply the acquisition or the renting of a pre-fabricated building (because building of a new infrastructure would be over costly).

The equipment repositioning process also has some associated costs but those, when compared with the acquisition of a new infrastructure, have a smaller impact. The new suggested layout has various advantages.

Moving the cutting machine into the new location would reduce the transportation time of the cut steel plates towards the steel shop, the panel line and the block manufacturing park.

The increase of the available space for outfitting related activities due to the creation of a new outfitting shop, it will also enable the suitable conditions for the implementation of more space demanding activities, as it is the case of the assembly of piping segments in modular units.

This space increment will also result in the reinforcement of the piping hub role of that shipyard's area. Concentrating all the piping activity on this area will create a logistic center that can supply all the construction needs both in ramps and piers.

4.3.3 Cost Comparison

Cost comparison was expressed in differences in traveling time between workstations. Following the logic defined by Muther [12] and mentioned in subsection 2.3.3.3, there are three types of fields on which cost comparison is made upon.

- **Flow Index**
- **Transport Work**
- **Definitive material handling cost**

The cost comparison study started by analyzing the existing traditional outfitting layout in order to define a reference/control layout. The results obtained from this analysis provided the baseline values for the comparison with the new suggested modular outfitting layout.

Those results were exported from the software *Proplanner* and were used, both for flow index and transport work calculations.

The estimation of the definitive material handling costs would imply a more detailed analysis, that would require a high level of expertise, concerning the position and the working rate of several units inside the shops and the material handling methods (for plates, pipes, stiffeners, small sized equipment, large sized equipment, and other equipment and materials). Therefore, it was considered out of the scope of this master's thesis.

Flow index was defined upon the theoretical procedures mentioned on subsection 2.3.2.

Two types of flow index outputs were obtained:

- i. **The Relationship Chart**
- ii. **The Space Relationship Diagram**

These outputs were generated for both the existing traditional outfitting layout and the suggested modular outfitting layout.

Starting by the existing traditional outfitting layout, it has been stated that every piece of material and equipment arrives in the reception park; thus, this park has type “A” relationship rates with several shops and construction sites (construction ramp and pier).

The shops and the facilities (construction ramp, block manufacturing park, steel shop, panel line and cutting shop) where the block manufacturing process is performed also have type “A” and “E” relationship rates among them.

Regarding piping systems, currently the pipes are outsourced and manufactured outside the shipyard. Hence in the shipyard they are merely assembled and tested on board. Additionally, if they have some type of damage in terms of surface treatment, they might also be blasted and painted inside the shipyard. Consequently, most of the pipe related flow in the shipyard occurs between the reception park and the construction sites.

By observing table 4.2 a broader insight regarding the existing layout relation rates can be obtained.

A Space Relationship Diagram for traditional outfitting existing layout was created, using the data from the Relationship Chart (figure 4.2), as represented by figure 1 of annex B. To avoid the diagram lines overload only “A” type relations were drawn.

Several changes of the suggested new layout were advocated as mentioned in 4.3.1. Having created a new shop and having redefined activities flow, logically, new relationship rates had to be delineated, then, a new relationship chart was created.

Several relation rates can be highlighted in this new relationship chart (figure 4.3). First, the detach of a new outfitting shop that due to its new functions is now the construction sites pipes supplier. Hence this shop has kept an “A” type relation rate with the block manufacturing park and with the construction ramp.




Figure 4-2: Existing TO layout relationship chart

Another example of a new relations rate that can be highlighted on this new modular outfitting layout is the relation concerning the steel park. The creation of this park redefined the relations between the facilities that take part on the block manufacturing process.

In the existing traditional outfitting layout, the steel shop and the panel line, were supplied by the reception park, with a type “A” relationship with the shops, while in the new modular outfitting layout they receive their materials from the steel park, also with a type “A” relationship, but within a significant shorter distance of 41 meters instead of 65 meters.

More details regarding the established relations of this purposed layout is provided by figure 4.3.




Figure 4-3: Suggested MO layout relationship chart

Using the data from Relationship Chart (figure 4.3) a Space Relationship Diagram was created for suggested modular outfitting layout as represented in figure 2 of annex B. To avoid the diagram line’s overload only “A” type relations were drawn.

Based on the modular outfitting space relationship diagram, the routes distances between the workstations for the suggested modular outfitting layout were measured.

The routes distances between the workstations for the suggested traditional outfitting layout have been measured based on the respective space relationship diagram. Table 4.4 displays the distance values and the compared differences between layouts.

The mobile equipment traveling average speed when carrying loads has been collected resulting on an average speed of 1.21 m/s. The traveling times were determined, using this speed and knowing the distances between workstations.

The results regarding the modular outfitting layout transport work, considering the routes differences discriminated in table 4.5, showed that the outcome of change no. 1 and change no. 3 was a very significant reduction of traveling time when compared with the former traditional outfitting layout disposal. Looking in detail, the traveling time between the place where steel was storage in the previous layout

and the place where it would be storage in the suggested modular outfitting layout (near to the new cutting machine location), decreased by **37%**. The traveling between the cutting machine and the steel shop had a remarkable decrease of **75%**.

Table 4-4: Trip distances between workstations

		Cutting machine position 1		Cutting machine position 2	
From	To	Trip Distance (m)	To	Trip Distance (m)	
Cutting machine	Pre- fabrication	111.7	Pre- fabrication	38.12	
	Receiving park (P1)	65.25	Steel storage park	41.05	
	Steel shop	118.83	Steel shop	29.22	
	Construction ramp	127.34	Construction ramp	105.61	

Table 4-5: Traveling times between workstations

		Cutting machine position 1		Cutting machine position 2		
From	To	Travel Time (s)	To	Travel Time (s)	Relative Difference	
Cutting machine	Pre- fabrication	93.08	Pre- fabrication	31.77	66%	
	Receiving park (P1)	54.38	Steel storage park	34.21	37%	
	Steel shop	99.02	Steel shop	24.35	75%	
	Construction ramp	106.11	Construction ramp	88.01	17%	

Figure 4.4 and 4.5 display the flow charts of the process to be implemented in the suggested layout. The changes between the existing and suggested layout would allow a smooth implementation of both, the module structure manufacturing and assembly process (figure 4.5) and the module assembly process (4.4).

In the case of the module structure manufacturing, the work flow gain margin from the repositioning of the cutting machine would depend of the number of parts and pieces to be cut, however, it is secure to state that it would be positive, when compared with the existing layout.

In the case of the module assembly process it is not possible to perform a gain margin comparison between existing and suggested layout because it is a new process that was not contemplated in the existing layout.




Figure 4-4: Suggested MO module assembly flow chart




Figure 4-5: Suggested MO module structure assembly flow chart

5

5 Modular Outfitting Implementation Risk Management

Contents

5.1	Scope of the problem	66
5.2	Methodology	66
5.3	Results Analysis.....	70

This chapter describes a Risk Management procedure that was undertaken to assess the implementation of modular outfitting construction approach.

It addresses in particular the processes of: Risk Identification, Qualitative Analysis and Risk Response and Critical Success Factors.

Critical Success Factors, CSFs for this outfitting practice are also described in detail, because they are decisive and crucial to obtain positive results, in order to achieve the established objectives and to achieve success.

5.1 Scope of the problem

The definition of risk and the need to measure risk before initiating any kind of action was developed in section 2.4.

Thus, like in any project, when implementing a new type of production technique or approach in a shipbuilding process it is necessary to identify, assess and manage the risks of the new project.

Therefore, the following three questions are addressed in this chapter:

- **What are the existing risks of Modular Outfitting Approach?**
- **What is the likelihood and impact of those risks?**
- **How to operate to respond to that risk?**

5.2 Methodology

To answer the questions formulated in the previous sections, it was necessary to identify the risks, to perform a qualitative analysis and to develop a risk response table. These analytic tools are part of the risk management procedure (see section 2.4).

5.2.1 Risk Identification

The first step taken was the risk identification. Modular Outfitting approach is composed by seven different processes and each one has specific risks that result from specific causes.

1. **Design**
2. **Module parts manufacturing**
3. **Module assembly**
4. **Dimensional control and running tests in shop**
5. **Module transportation and fitting on-block**
6. **Block assembly, fitting and installing**
7. **Final trials**

Figure 5.1 graphically shows the workflow of Modular Outfitting including the sequence decision points.




Figure 5-1: Modular outfitting workflow

5.2.2 Qualitative Analysis

For each process described in subsection 5.2.1, identified risks impact was quantified and, the risk's likelihood was assessed.

Once having assessed both the factor of risk impact and of risk likelihood, a final risk score for each identified risk was obtained as described in the following sections.

Risk score is the intended output that allows measuring risk, grading and representing it in an impact-likelihood table.

5.2.2.1 Risk Impact

The methodology of Guedes Soares/Gomes Lopes [15] described in section 2.4 was used to quantify the impact associated to each identified risk.

The project's impact analysis depends on Quality, Cost and Time (when applicable to the identified risk) using a scale of risk impact quantification from 0 to 3.

The total **Risk Impact** (I_{risk}) was obtained for each identified risk by summing the impact ratings for Quality, Cost and Time factors that define the sustainability of the project (equation 5.1).

$$I_{risk} = I_Q + I_T + I_C \quad (5.1)$$

In which:

I_Q - Quality factor

I_T - Time factor

I_C - Cost factor

Once each risk had been rated, the obtained values (that could vary within a range from 0 to 9) were normalized into an impact rating scale from 1 to 5. Normalization was performed by dividing each total impact rating by the highest rating value generated and then multiplying this value by five.

The final result was rounded up to the unit (equation 5.2).

$$I_{risk} = I_Q + I_T + I_C \quad (5.1)$$

$$I_{normalized} = \frac{I_{risk}}{\max I_{risk}} \cdot 5 \quad (5.2)$$

Where:

I_{risk} - Total impact factor score for each identified risk (equation 5.1)

$\max I_{risk}$ - Maximum total impact factor score of all identified risks

Impact was measured in a scale of rating within a range of 1 to 5, that correspond to the impact categories of low (rating equals 1 or 2), medium (rating equals 3), medium-high (rating equals 4) and high (rating equals 5)

5.2.2.2 Risk Likelihood

The other input of the qualitative analysis is the likelihood of risk occurrence. Like in the risk impact, likelihood was expressed in a scale of likelihood scores within a range of 1 to 5, that correspond to the likelihood categories of low (rating between 1-2), medium (rating equals 3), medium-high (rating equals 4) and high (rating equals 5). The likelihood of occurrence of each identified risk was empirically estimated.

5.2.2.3 Risk Assessment in function of risk Impact and Likelihood

The risk assessment was based on the impact-likelihood risk score results, computed by equation 5.3.

$$RiskScore = Likelihood \cdot Impact \tag{5.3}$$

The likelihood-impact tables developed in the qualitative analysis of this dissertation’s was based in PMBOOK qualitative risk assessment approach [14], although adapted.

In the PMBOOK approach [14], the likelihood rating range is between 0 and 1 points and the and impact rating range is between 0 and 0.1 points (table 5.1). The resulting impact-likelihood scores are classified and highlighted in a scale of color. In this scale the highest risk scores are represented by a red color, the lowest risk scores are represented by a green color, and the remaining risk score results are represented by intermediate colors that show the magnitude of the score by a color *degradé*.

Table 5-1: Example of a PMBOOK Impact-Likelihood table [14]

		IMPACT *				
		0.05	0.1	0.2	0.4	0.8
LIKELIHOOD	0.9	0.05	0.09	0.18	0.36	0.72
	0.7	0.04	0.07	0.14	0.28	0.56
	0.5	0.03	0.05	0.1	0.2	0.4
	0.3	0.02	0.03	0.06	0.12	0.24
	0.1	0.005	0.01	0.02	0.04	0.08

* Over an objective Ex: Cost, Time, Scope, Quality

Color code	0.005	0.01 - 0.02	Low Magnitude	0.03 - 0.04 0.05 - 0.07 0.08 - 0.1 0.12 - 0.14	Medium Magnitude	0.18 - 0.36 0.56 - 0.72	High Magnitude
------------	-------	-------------	---------------	---	------------------	----------------------------	----------------

In this dissertation’s, the likelihood rating range is between 1 and 5 points, which has a linear relation with the mentioned PMBOK rating range of 0 to 1 point.

Same procedure was applied to the impact scale. In the PMBOK approach, the impact range is between 0 and 0.1 point, but in this dissertation’s impact range is between 1 and 5 points, which once again is a linear function of the PMBOOK impact scale.

This increase of the scale points from 1 to 5 aimed to improve the ability to identify in detail the relative differences between the values of risk impact and of risk likelihood.

For each of these two dimensions of risk assessment, the rating values were categorized in low (rating equals 1); medium (rating between 2-4) and high (rating equals 5). No color scale was adopted for the Impact-Likelihood scores.

The range of values of risk score computed according to equation 5.3 is from 1 to 25 points.

On section 5.3 the identified risk will be exposed with their risk score and proposed risk response.

5.2.3 Risk Response

As stated in section 2.4 a risk can be managed by one of the following strategies: **Acceptance (A)**, **Mitigation (M)**, **Transfer (T)** and **Avoidance (I)**. The selection of the response strategy is respectively based on the increasing magnitude of the impact and on the likelihood of the risk. Thus, due to the existing relation between response and the risk factor's magnitude, a risk response selection table (table 5.9) was created according to the impact-likelihood risk score.

The response for each of the identified risks was developed according to risk score (impact-likelihood relation). A color code was adopted according to the proposed risk strategy: green for Acceptance (A), yellow for Mitigation (M), orange for Transfer (T) and red for Avoidance (I).

5.2.4 Critical Success Factors (CSFs)

Critical success factors were defined based on their possibility to influence the results obtained from the qualitative risk analysis. In other words, the CSFs were selected considering their potential to reduce the risk of the identified risks.

In annex C table C.1 it is displayed the CSF's associated to each identified risk.

5.3 Results Analysis

5.3.1 Identified Risks

Risk analysis by process was based on the modular outfitting workflow (Figure 5.1), and each identified risk was numbered with a 2 digit code in which the first digit refers to the process number. The risks identified are described in this section and summarized in tables 5.2, 5.3, 5.4, 5.5, 5.6, 5.7 and 5.8.

5.3.2 Qualitative Analysis

As stated in the methodology, particularly in subsection 5.2.1, the 27 risks were identified for seven different processes.

The qualitative analysis of the risk impact and likelihood factors was described in subsection 5.2.2.1. On annex B, table C.1 the risk impact results obtained from the methodology used in [15] are displayed in detail, and the impact results were displayed in table C.2 side by side with the likelihood results. Final risk score for every identified risk (left to right fifth column in tables 5.2 to 5.8) was obtained by using equation 5.3.

5.3.2.1 Design Processes

The risks identified in the design process are displayed in table 5.2.

The design process is of most importance because it occurs in an early project phase where fundamental decisions are taken and whose consequences are cumulative along all project phases.

Although with a low likelihood, design identified risks 1.1 and 1.6 might have a high impact both in terms of deadlines compliance and in terms of budgeting control, as shown in chapter 2 figure 2.1 through a chart of influence of each phase on ship's lifecycle costs.

Table 5-2: Design Process Identified Risks

		Likelihood	Impact	Risk Factor	Risk Response
1	DESIGN				
1.1	Poor identification of equipment and outfitting components forming in modular block	2	5	10	M
1.2	Lack of preliminary and further studies in outfitting modular implementation strategy	4	4	16	M
1.3	Unexperienced designers on conceptual production manufacturing	2	3	6	M
1.4	New procedures and techniques	2	1	2	A
1.5	Inadequate working plans, production and detail drawings	4	5	20	T
1.6	Inadequate inspection and control methodology	1	5	5	M

Poor identification (or design) of equipment and outfitting components forming in a modular block (risk 1.1) could imply, not only delays but also additional costs related to rework during the construction phase.

Inspection and control step is a well-established risk, so it has low likelihood of not being adequate to verify compliance with the requirements, but in case of not being able to scope errors, it is prone to have a high impact.

In what concerns inadequate working plans, production and detail drawings (risk 1.5), there is a medium likelihood of not being possible, at a very early phase, to anticipate with accuracy every practical requirement. Flaws in design process have a high impact in all subsequent modular outfitting processes

5.3.2.2 Module Parts Manufactured Process

The process of the manufacturing of module parts (as well as the process of module assembly) is mostly susceptible to risks related with quality control and with schedule compliance by the supplier-s/outsourced entities.

.In what concerns quality control, the risks are the existence of elements out of form, out of dimensions, and with welding faults. The high impact of these risks results from the probability of identification of faulty parts on advanced phases of assembly, or from the possible delays resulting from the need of reordering the defective parts. Although having a high impact risk, they have a low likelihood due to the certified compliance of the product manufacturing entities (shipyard pipe suppliers) with the quality standards. The identified risks of Module Parts Manufactured are displayed in table 5.3.

Table 5-3: Identified Risks of Module Parts Manufactured

		Likelihood	Impact	Risk Factor	Risk Response
2	MODULE PARTS MANUFACTURED				
2.1	Equipment and raw material delivery out of date	5	2	10	M
2.2	Piping elements and structural elements, out of forms and dimensions	1	5	5	M
2.3	Welding joints faults	2	4	8	M
2.4	Equipment delivery without running tests	1	4	4	M

5.3.2.3 Module Assembly Process

As mentioned in the above subsection 5.3.2.2, this subsection identified the risks related to quality control. For the reasons explained above the risk impact is medium or high and the likelihood is medium. Module assembly identified risks are displayed in table 5.4.

Table 5-4: Module Assembly Identified Risks

		Likelihood	Impact	Risk Factor	Risk Response
3	MODULE ASSEMBLY				
3.1	Parts out of dimensions	1	5	5	M
3.2	Parts out of shapes	1	5	5	M
3.3	Components missing	3	3	9	M
3.4	Components misaligned	3	3	9	M

5.3.2.4 Dimensional Control and Running Tests in Shop Process

Dimensional Control and Running Tests in Shop identified risks are displayed in table 5.5.

The risks of dimensional control and running test have high likelihood and medium impact. These factors have this order of magnitude for two reasons:

- I. First, the high likelihood derives from potential leaking and from adjustments on pipe flanges (risk 4.2) required by the results of hydraulic tests. The magnitude of impact of leakage derives from the potential delays due to adjustments or rework required by leakage test failure.
- II. Second, the high likelihood, as well as the medium impact of risk 4.1 (module isometric check points out of dimensions) results from misalignments, which are quality related risks with a high chance of occurrence.

Table 5-5: Dimensional Control and Running Tests in Shop Identified Risks

		Likelihood	Impact	Risk Factor	Risk Response
4	DIMENSIONAL CONTROL AND RUNNING TESTS IN SHOP				
4.1	Module isometric check points out of tolerance in the three-dimensional measurement	5	3	15	M
4.2	Hydraulic tests failure due to leakages	4	4	16	M

5.3.2.5 Transportation and Fitting On-Block Process

The risks of module transportation and fitting on-block process concern two different procedures: the hoisting related procedures (risks 5.1, 5.2 and 5.3) and the fitting procedures (risks 5.4, 5.5 and 5.6).

In hoisting, the risks are associated to noncompliance with the operating safety rules and to noncompliance with the material safety rules. Employee's vehicle and crane handling certification along with the regular update of the certificated licenses are critical practices regarding risk increase avoidance.

Fitting procedures are the ones that have the highest risk score, both in terms of impact and of likelihood.

The procedure of most importance in modular outfitting approach is the correct scheduling between two parts of integrated construction (risk 5.5): the block manufacturing (part of the hull block construction method) and the module assembly (part of zone outfitting method).

Defective coordination between the two mentioned parts of integrated construction could result in severe delays and added costs, by holding other process parts. An example of a critical situation would be holding the start of a new block assembly process due to delays in the outfitting modules that were to be fitted on a previous block (that would remain for a longer time in the construction park).

Besides scheduling risks, on block fitting procedures has other risks such as potential interferences with other equipment/structures as a result of misalignment of boundary spaces and also as the existence of damaged parts (which implies removing, manufacturing and re-assemble that same part).

Both these identified risks have high likelihood and medium impact, due to the probable need of rework triggered either by the misalignment correction or by damage component substitution.

Transportation and Fitting On-Block identified risks are displayed in table 5.6.

Table 5-6: Transportation and Fitting On-Block Identified Risks

		Likelihood	Impact	Risk Factor	Risk Response
5	MODULE TRANSPORTATION AND FITTING ON BLOCK				
5.1	Overloading for available hoisting equipment	2	3	6	M
5.2	Laid-up and laid-down failure	2	1	2	A
5.3	Handling operation performed without qualified people	2	5	10	M
5.4	Misjudgment of boundary spaces offsets (interferences)	4	4	16	M
5.5	Schedule coordination between Block and Module Block failure	5	5	25	I
5.6	Components damages	5	3	15	M

5.3.2.6 On-Block Assembly Process

On block assembly process has two types of risks: risks related with module parts manufacturing **and dimension and shape compliance** (risk 6.1, 6.2 and 6.3) and with **module misalignment identified during modules position checking** (risk 6.4 and 6.5).

- First type of risk has high impact, as on-block assembly is a chronological advanced process, hence, all corrections have serious impact in schedule compliance. Likelihood is of medium magnitude, because of the multiplicity of systems parts and pieces, which, even within quality standards, have the potential to increase the possibility of defective components. Dimension and tolerance checking has medium likelihood factor and medium impact factor. In terms of impact, the main reasons for medium impact value is related with the temporary holding due to other processes (such as painting). The ground for this impact evaluation derives from the reasons detailed below. The on-block assembly process is performed just before the block erection phase. This assembly process is developed after the assembly of most of the block's structures and developed in simultaneous with the finishing works of the block. Therefore, the existence of corrections in the modules could imply holding other processes that are being developed near the modules place or that use shared equipment/tools with those modules (example: Cranes, welding machines, cutting machines, and others). Likelihood is considered medium because there could be numerous modules to be fitted on-block and therefore, there is an increased the possibility of misfitting modules.
- Concerning module misalignment, the existence of module isometric checkpoints out of tolerance risk has a high likelihood and a medium impact. These assembly isometric check procedures have a high likelihood due to the cumulative factor. At this point of the overall process, numerous units have already been manufactured and assembled; therefore, multiple defective assemblies may have been performed. Thus, in case of significant defective assembly, a considerable amount of parts has to be refitted, which from the point of view of this risk analysis will also be translated in to a medium impact.

On-Block Assembly identified risks are displayed in table 5.7.

Table 5-7: On-Block Assembly Identified Risks

		Likelihood	Impact	Risk Factor	Risk Response
6	ON BLOCK ASSEMBLING				
6.1	Parts out of dimensions	4	5	20	T
6.2	Parts out of shapes	4	5	20	T
6.3	Components missing	4	3	12	M
6.4	Block isometric check points for installing block module out of tolerances	4	3	12	M
6.5	Block isometric check points for piping connection out of tolerances	4	3	12	M

5.3.2.7 Final Trials Process

Final tests and trials have medium likelihood and medium impact due, once again, to the cumulative factor. Some defects might have passed on through the entire modular outfitting assembly workflow which might imply retroactive action all along the six previous processes of modular outfitting.

In table C.2 all the identified risks with their impact factor, likelihood factor and risk score are displayed (Risk response is also displayed but it only concerns subsection 5.3.3).

Final Trials identified risks are displayed in table 5.8.

Table 5-8: Final trials identified risks

		Likelihood	Impact	Risk Factor	Risk Response
7	FINAL TRIALS FAILURE	2	4	8	M

5.3.2.8 Most relevant modular outfitting risks

The rationale behind the identification of the most relevant modular outfitting risks was to select the risks with the highest values of the risk score.

The modular outfitting most risk affected processes were:

Process 1 - design process

Process 4 - dimensional control & running test in shop

Process 5 - module transportation & fitting on block

Process 6 - on-block assembly, fitting and installing process

The greatest modular outfitting identified risks are listed below in a descending order of risk score:

Identified Risk **5.5**

(Schedule coordination between block and module block failure)

Risk score of 25

likelihood = 5; impact = 5

Identified Risk **1.5**

(Inadequate working plans, production and detail drawings)

Risk score of 20

likelihood = 4; impact = 5

Identified Risk **6.1**

(Parts out of dimension)

Risk score of 20

likelihood = 5; impact = 4

Identified Risk **6.2**

(Parts out of shape)

Risk score of 20

likelihood = 5; impact = 4

Identified Risk **4.2**

(Hydraulic tests failure due to leakages)

Risk score of 16

likelihood = 4; impact = 4

Identified Risk **1.2**

(Lack of preliminary and further studies)

Risk score of 16

likelihood = 4; impact = 4

Identified Risk **4.1**

(Module isometric check points out of tolerance in the 3-D measurement)

Risk score of 15

likelihood = 3; impact = 5

Identified Risk **5.4**

(Misjudgment of boundary spaces offsets -interferences)

Risk score of 16

likelihood = 4; impact = 4

Identified Risk **5.6**

(Components damages)

Risk score of 15

likelihood = 5; impact = 3

5.3.3 Risk Response

Risk response was made in consonance with the methodology exposed in sub-section 5.2.3.

For each identified risk a standardized type of response was assigned: Acceptance (A), Mitigation (M), Transfer (T) or Avoidance (I), as defined in section 2.4.

Risk 5.5 – “schedule coordination between block and module block failure” had the highest risk score (25 points) and it was the only risk that has to be contained by an avoidance response. This Step of the Transportation and Fitting On-Block process must be carefully planned, checked and identified risk corrective and preventive measures must be implemented.

Risks 1.5, 6.1 and 6.2- had high risk score (20 points) and should be handled by transfer response. These factors had to be covered by entities outside the shipyard. The risk factor is high and the attempt to mitigate could jeopardize parts of the overall outfitting process.

Risks 4.1, 4.2, 5.4 and 5.6 - have a medium impact but a high likelihood (15-16 points), so except for risk 1.2, the response should be mitigation or reduction of its consequences by establishing acceptable limits together with a recommendation that the shipyard should endeavor all efforts to comply with them.

Risk 1.2 - has a medium/high score of risk, that respects design flaw (which might influence the entire assembly process of outfitting systems), due to the fact that critical design flaws are identified by

surveyors and designers, hence, only medium to small errors will prevail to the next phases of the outfitting assembly process.

Risks 2.1, 3.3, 3.4, 6.3, 6.4, 6.5 and 7- have medium risk score (10-12 points), due to both medium impact and medium likelihood, so they are also suitable to be managed by a mitigation response. Risks 6.4, 6.5 and 7 are medium impact risks connected to checks and tests to the processes. These risks are associated with the likelihood of having already performed a considerable amount of cumulative work before verifications and with the possibility of rework need. Generally, the detected errors are minor and easy to fix so their existence won't jeopardize the outfitting process.

Risk 3.3 and 3.4 – are medium impact risks related with lack of components and components misalignment. They are not critical risks, because it seldom puts on hold the module assembly process/on-block assembly process although it may create small delays and added costs.

Risks 1.4 and 5.2 - have a low likelihood and a low impact factors, therefore the shipyard should accept them without pointless spending of resources.

Risk 1.4 - is a clear example of a result of continuous progress of the shipbuilding industry. Although, each entity should try to keep-up as much as possible with the most *avant garde* techniques and procedures, the added value of a new technique implementation must be judged properly, in order to manage the risk and get a return on investment. Hence, in case of unacceptable costs with marginal advantages, sometimes innovation is not worthless to be implemented, allowing resources spare and reallocated to breakthrough changes.

Risk 5.2 - results from handling heavy loads in open spaces that are mainly influenced by weather conditions. Therefore, small accidents, like small damage on the modules structure due to impact resulting from hitting the modules berths, as long as they do not jeopardize the workers safety, are accepted.

As per above described the most common risk response is mitigation, which requires an accurate technical sound judgment to define acceptable limits and a robust compliance assurance to guarantee the quality that he defined limits are respected.

Table 5.9 shows graphically the identified risks disposed according to their risk score in a likelihood-impact table, with the response color code included.

Table 5-9: 27 identified risks likelihood-impact table
(Coloured according to response color code)

		Impact Factors				
		1	2	3	4	5
Likelihood Factors	5	2.2	2.1	5.6	6.1; 6.2	5.5
	4	2.4	2.3	6.5	1.2; 4.2; 5.4	1.5
	3		5.1	3.3; 3.4	6.3; 6.4	4.1
	2	1.4		1.3	7	1.1; 5.3
	1		5.2			3.1; 3.2

5.3.4 Critical Success Factors

These CSFs are risk related success factors that were defined based on the assumption that if the identified major risks were controlled the remaining of the modular outfitting processes would be smoothly developed and will not jeopardize the shipbuilding process.

However, it does not exclude the existence of other CSFs resulting from top management and strategic decisions. Annex B (figure C.2) displays the identified risks that are influenced by the CSFs described below.

These CSFs were defined by Moura and Botter [21]. They are CSFs for the Brazilian shipbuilding industry that can be also applied in the Portuguese industry and specifically to the “Haksolok” construction process.

The list of the selected nine critical success factors is the following:

- F1:** Application of CAD systems for project development;
- F2:** Supplier inclusion during project’s production design phase
- F3:** Send the production planning in advance to the suppliers
- F4:** Implementation of delivery schedule compliance control mechanisms (suppliers)
- F5:** Standardization of supplier provided parts and equipment
- F6:** Tech partnership in research and development area between the shipyard and the suppliers
- F7:** Partnership in research development area between the shipyard and the universities
- F8:** Presence of qualified labor force
- F9:** Equipment and machinery technological update

F8 and F9 are the most outstanding because of their influence on a large number of the identified risks, including risk 5.5, which is the most hazardous identified risk.

Factor F8 concerns the presence of qualified labor force, which is a fundamental requirement because it influences positively all the shipyard’s quality and safety indicators. This factor is display in every quality and safety international standards.

Factor F9 is relative to machinery technological updates. With well-defined criteria, based on the production experience of the shipyard, the strategical machinery updates could represent a significant increase of production indexes.

Factors F3 and F4 have direct impact on identified risk 5.5 therefore there are defined as off most importance within the CSF’s list.

Both factors F3 and F4 relate with supplier’s delivery scheduling and controlling. These factors are of most importance during all the outfitting assembly phases, especially in what concerns phases of grand assembly as the ones covered in identified risk 5.5.

6

6 Conclusion

Contents

6.1	Conclusions	82
6.2	Future Work	84

6.1 Conclusions

As stated in the introduction, the scope of work of this dissertation is to analyze the bilge's system assembly performed by traditional outfitting production methodology in a ferry vessel (Haksolok built using traditional outfitting at Atlantic Eagle Shipbuilding shipyard), and to compare it with same system assembled and performed by modular outfitting production methodology.

This study aimed to answer three questions by:

- i. Comparing the workload expressed in Man-hours between traditional on-board outfitting and modular outfitting on-block approach
- ii. Defining the layout changes required by the implementation of modular outfitting processes *versus* the implementation of traditional outfitting process according to SLP analysis that includes the comparison of costs derived from the distances and routes of the existing layout *versus* the distances and routes of the modular outfitting adapted layout;
- iii. Identifying and managing risks associated to modular outfitting implementation, and by defining the CSFs for effective implementation of modular outfitting approach.

Regarding the first question the study suggested that by implementing the modular outfitting approach, the number of Man-hours used in the assembling procedure could be reduced by 549 Man-hours, which represents a gain of 74% when compared with traditional outfitting, as per section 3.3.

In what concerns the second question, about Systematic Layout Planning for modular outfitting implementation, it can be concluded that there are more direct and indirect advantages resulting from the new suggested layout namely in what respects distance between work stations, space for outfitting related activities and outfitting work flow hub creation.

It should be enhanced that the positioning of the cutting machine near the steel shop (using a pre-fabricated building) and the creation of a new steel storage park nearby the steel shop will represent an improvement in terms of traveling time. The route traveling time between the cutting machine and the steel shop, on the new suggested layout, enables a trip reduction of 75% when compared with the trip time of the existing layout, as per section 4.3.3. (table 4.5)

This newly suggested cutting machine position will also decrease the traveling times for the panel line by 66% and for the construction ramp it has a reduction of 17%, as per section 4.3.3 (table 4.5).

Another important matter is the location of the new steel storage park. The repositioning of the site to storage the steel plate and steel profiles will result in the decreasing of trip's time between the park and the different buildings. Comparing with the existing layout this advocated alteration will bring a traveling time decrease of 37% on the route towards the cutting machine, as per section 4.3.3 (table 4.5).

An indirect advantage derived from the suggested layout changes would be the creation of a new outfitting shop on the former location of the cutting machine. On the existing layout there was already an outfitting shop that would be kept (located side by side with the shop where the cutting machine shop used to be). This new outfitting shop, derived from the need to repositioning the cutting machine, was

planned to be the location where the outfitting modules would be assembled. This new shop along with the previous outfitting shop would enable the shipyard to have adequate facilities to implement the modular outfitting approach and to benefit from the expected production gains due to reduction of the trip time, without having significant added costs (since the new location of the cutting machine would be a pre-fabricated building). Another important benefit would be the creation of an outfitting hub, that would simplify the routes network of the work flow by centralizing outfitting related activities in a single shipyard zone and by subsequently reducing the work flow routes dispersion.

An advantage of traditional outfitting layout, that is simultaneously a disadvantage of modular outfitting layout, is the distance between the cutting machine and the repair ramp but considering that most of the times the path of plates is not directly towards the construction ramp, it only should represent a minor flow disruption.

The major disadvantage of modular outfitting layout is that it generates additional costs to rent/acquire the pre-fabricated building to host the cutting machine.

In respect to the third question regarding risk management of modular outfitting implementation, there are seven processes that can be the source of risk in modular outfitting: 1) Design; 2) Module Parts Manufacturing; 3) Module Assembly; 4) Dimensional Control and Running Tests in shop; 5) Module Transportation and Fitting on-block; 6) Block Assembly, Fitting and Installing and 7) Final trials.

There are six processes for risk management: 1) Risk Managing Planning; 2). Risk Identification; 3) Qualitative Risk analysis; 4) Quantitative Risk analysis; 5) Risk Response Planning and 6) Risk Monitoring and Control.

This study addressed the processes of: 2) Risk Identification, 3) Qualitative Analysis; 5) Risk Response and Critical Success Factors.

Every identified risk was scored according to the value of the product of its impact (function of quality, cost and time) and its likelihood and a risk response was developed according to the level of severity (low, medium; high medium and high) of these risk components..

The most critical risks identified, were related with the design process, with the dimensional control and running test in shop process, with the Module Transportation and Fitting on Block process and with the On-block assembly fitting and installing process. The higher risk score regards risk 5.5 - Effective Schedule Coordination between Block and Module Block identified risk (Module Transportation and Fitting on Block process) that must be managed by an avoidance response that implies its careful planning, checking and implementation of corrective and preventive measure.

To control the major identified risks a list of nine critical success factors was defined: **F1:** Application of CAD systems for project development; **F2:** Supplier inclusion during project's production design phase; **F3:** Send the production planning in advance to the suppliers; **F4:** Implementation of delivery schedule compliance control mechanisms (suppliers); **F5:** Standardization of supplier provided parts and equipment; **F6:** Tech partnership in research and development area between the shipyard and the suppliers; **F7:** Partnership in research development area between the shipyard and the universities; **F8:** Presence of qualified labor force and **F9:** Equipment and machinery technological update.

F8 and F9 are most critical due to their influence on a larger number of identified risks including risk 5.5. The risk management analysis performed shows that this profitable outfitting methodology can be implemented, although it carries critical risks that must be addressed. Strong planning, quality certification, scheduling margins and investment in labor force qualification and training would be factors that would reduce the risk factors of this outfitting approach.

If implementing modular outfitting approach, the shipyard should therefore incorporate the described CSFs in their strategic objectives and monitor performance accordingly.

6.2 Future Work

According to this study, the implementation of modular outfitting approach seems to have the potential to represent a significant decrease of the number of used Man-hours when compared with traditional outfitting methodology. The necessary layout changes for implementing this modular outfitting methodology do not seem to add significant costs and might reduce traveling time between workstations, both in the outfitting processes and in the block manufacturing processes. Additionally, the modular outfitting implementation has a moderate risk although it can be manageable.

However, this dissertation raises some unanswered questions that could be develop in future studies.

Complementary studies could address the designing phase workload of Outfitting (modular) in integrated construction that is associated with a substantial amount of workload increase and the Module structure manufacturing and welding to the fitting birth in the bilge system modular outfitting work flow computations in order to accurately determine its impact on the outfitting workload.

Regarding chapter 3, the calculations, of the Man-hours concerning traditional outfitting assembly method was a complex process that had to be based in technical drawings, empirical data collected from different authors mentioned in the literature, to define compensation factors based on the ship's characteristics and that had to assume an empirical coefficient for the conversion of Man-hours from traditional outfitting to modular outfitting depending on pipe's curves and branches, as well as in what concerns pipe sections copulated equipment and valves. The experimental determination of these coefficients could be developed in a future on-field study to systematize data on assembly, fitting and installing Man-hours calculations.

Butler's [17] work provided data on pipe repair Man-hours collected in large dimensions shipyards that were used in this study due to the lack of similar national data more suitable for smaller and medium dimension shipyards. The generation of this data can also be the scope of future research work.

The scope of the systematic layout planning analysis that was performed only included the major shipyard's activities (cutting, outfitting, block assembly and others). Each of this major activity is divided into smaller sub activities that were not included in this study. A more comprehensive SLP analysis could be extended to sub activity level.

Finally, in this dissertation, only three out of six phases of risk management were assessed. Future work could consist in extending the analysis to the other phases (1) Risk Managing Planning; 3) Qualitative Risk analysis; and 6) Risk Monitoring and Control).

Bibliographic References

- [1] R. Rubesa, N. Fafandjel, and D. Kolic. "Procedure for estimating the effectiveness of ship modular outfitting," *Engineering review*, vol. 31, no. 1, pp. 55–62, 2011.
- [2] C. Chapman and S. Ward. "Project risk management: processes, techniques, and insights", 2003.
- [3] F. Gomes Lopes. "Shipyard organization class notes," 2017.
- [4] B. Rocque. "Enabling effective projects sponsorship: A coaching framework for starting projects well," 1999.
- [5] R. Baade, F. Klinge, K. Lynaugh, F. Woronkowicz, and K.-M. Seidler. "Modular outfitting," *Journal of ship production*, vol. 14, no. 3, pp. 170–179, 1998.
- [6] M. Ozkok and I. H. Helvacioğlu. "Determination of the effects of the pre-outfitting and pre-piping assembly operations on shipyard productivity," *Polish Maritime Research*, vol. 20, no. 1, pp. 59–69, 2013.
- [7] T. W. Seubert. "Modular shipbuilding and its relevance to construction of nuclear power plants," *Tech. Rep.*, 1988.
- [8] N. Agarwala. "Developments in modular construction for shipbuilding," *Future Trends and Opportunities in Warship design and Construction*, 2014.
- [9] B. E. Altic, R. M. Burns, B. Fontaine, I. Scott, J. L. Silveira, and J. Softley. "Implementation of an improved outfit process model," *Journal of Ship Production*, vol. 19, pp. 1–7, 2003.
- [10] S. N. S. R. Program. *Design for zone outfitting*, 1983.
- [11] R. L. Storch, C. P. Hammon, and H. M. Bunch, "Ship production", 1988.
- [12] R. Muther and L. Hales. "Systematic Layout Planning/by Richard Muther and Lee Hales", *MIRP*, 4th edition, 2015.
- [13] C. G. Soares, A. Teixeira, P. Antão." *Fiabilidade Encontro Nacional de Riscos, Análise e gestão de riscos, segurança e fiabilidade*", 2005.
- [14] "Project management institute. a guide to the project management body of knowledge. *PMBOK Guide*", Project Management Institute, 4th ed., 2008.
- [15] C. Guedes Soares, F. Gomes Lopes, and J. Pedro Mendes. "Método para identificação e gestão de riscos em projectos de engenharia," *Riscos industriais e Emergentes*, pp. 291–307, 2009.
- [16] C. V. Bullen and J. F. Rockart. "A primer on critical success factors," *Center for Information Systems Research SLOAN School Of Management*, 1981.
- [17] D. Butler. "A Guide to Ship Repair Estimates in Man-hours", Butterworth-Heinemann, 2012.
- [18] C. W. P. O. SHIPBUILDING, "OECD directorate for science, technology and industry [sti]," 2007.
- [19] A. Fearnleys. "Review 2000," 2001.
- [20] J. S. Page. "Estimator's piping man-hour manual". Elsevier, 1999.
- [21] D. A. Moura and R. C. Botter. "Análise da competitividade da industria marítima brasileira: associação dos fatores críticos de sucesso com suas dimensões," *Produção*, vol. 21, no. 4, pp. 594–609, 2011.



7 Annex A

Pipe notation and calculation factors and final results in *Mh*

Table A.1: Pipe notation and calculation factors and final results in Mh

WBS	Yard Code	DN (mm)	Length (m)	Curves	Branch	Valves	Equipment	Reduction factor	Trend	TO Total Mh	MO Total Mh
1.1.1.1	041003	80	2.06	0	0.00	0.00	0.00	0.47	3.30	17.36	5.26
1.1.1.2	041003	80	1.78	0	0.00	0.00	0.00	0.40	3.26	15.85	4.86
1.1.1.3	041003	80	1.34	0	0.00	0.00	0.00	0.30	3.20	13.45	4.21
1.1.2.1	013001	32	0.81	0	1.00	1.00	1.00	1.52	3.98	5.47	1.37
1.2.3.1	041005	80	4.41	3	2.00	0.00	2.00	3.10	5.00	37.38	7.48
1.1.3.1	013002	32	2.61	1	0.00	0.00	0.00	0.74	3.48	10.45	3.01
1.1.3.2	013002	32	2.41	0	0.00	0.00	0.00	0.55	3.35	9.70	2.89
1.1.3.3	013002	32	3.37	5	0.00	0.00	0.00	1.48	3.96	13.59	3.43
1.1.4.1	011005	32	2.77	4	0.00	0.00	0.00	1.20	3.77	11.48	3.04
1.1.4.2	011005	32	1.70	0	1.00	0.00	0.00	0.72	3.46	8.20	2.37
1.1.5.1	011006	32	3.15	0	3.00	0.00	0.00	1.71	4.11	14.42	3.51
1.1.6.1	031002	80	2.04	0	0.00	0.00	0.00	0.46	3.30	17.26	5.23
1.1.6.2	031002	80	4.03	0	0.00	0.00	0.00	0.91	3.59	28.10	7.82
1.1.6.3	031002	80	1.74	0	0.00	0.00	0.00	0.39	3.25	15.60	4.79
1.2.1.1	069001	150	0.25	0	0.00	1.00	1.00	1.06	3.68	15.00	4.07
1.2.1.2	069001	150	0.11	0	0.00	0.00	0.00	0.03	3.02	13.53	4.49
1.2.1.3	069001	150	0.60	1	0.00	0.00	0.00	0.28	3.18	19.00	5.98
1.2.10.1	005001	32	4.11	4	1.00	0.00	0.00	1.84	4.19	16.76	4.00
1.2.10.2	005001	32	1.46	1	0.00	0.00	0.00	0.47	3.31	7.16	2.17
1.2.11.1	003001	32	0.91	0	0.00	0.00	0.00	0.21	3.13	5.54	1.77
2.3.7.1	105001	80	2.48	4	0.00	0.00	0.00	1.13	3.73	27.84	7.46
1.2.12.1	011002	32	0.96	2	1.00	0.00	0.00	0.84	3.54	6.05	1.71
1.2.12.2	011002	32	0.55	1	0.00	0.00	0.00	0.27	3.17	4.60	1.45
1.2.2.1	031004	80	2.54	3	0.00	0.00	0.00	1.01	3.65	21.12	5.79
1.2.2.2	031004	80	0.94	0	0.00	1.00	0.00	0.71	3.46	11.22	3.24
1.2.2.3	031004	80	1.46	3	1.00	2.00	0.00	2.09	4.35	15.57	3.58
2.3.2.2	041011	80	2.33	7	0.00	1.00	0.00	2.03	4.31	27.60	6.40
1.2.3.2	041005	80	1.34	3	0.00	2.00	0.00	1.73	4.12	13.99	3.40
1.2.4.1	029001	80	1.40	2	1.00	0.00	0.00	0.94	3.60	14.97	4.15
1.2.4.2	029001	80	1.38	2	0.00	0.00	0.00	0.60	3.39	14.07	4.15
1.2.5.1	029002	80	2.57	5	2.00	1.00	1.00	2.96	4.92	25.08	5.10
1.2.5.2	029002	80	0.11	0	0.00	2.00	0.00	1.03	3.66	6.74	1.84
1.2.6.1	107001	65	0.24	0	0.00	1.00	0.00	0.55	3.36	6.12	1.82
1.2.6.2	107001	65	0.10	0	0.00	1.00	1.00	1.02	3.66	5.48	1.50

Table A.1: Pipe notation and calculation factors and final results in Mh (continuation)

WBS	Yard Code	DN (mm)	Length (m)	Curves	Branch	Valves	Equipment	Reduction factor	trend	TO Total Mh	MO Total Mh
1.2.7.1	107002	65	0.27	0	0.00	1.00	0.00	0.56	3.36	6.24	1.86
1.2.7.2	107002	65	1.57	4	0.00	0.00	0.00	0.93	3.60	12.86	3.57
1.2.8.1	009001	32	0.53	1	0.00	0.00	0.00	0.26	3.17	4.53	1.43
1.2.11.2	003001	32	0.52	1	0.00	0.00	0.00	0.26	3.17	4.49	1.42
1.2.8.3	009001	32	1.36	1	0.00	1.00	1.00	1.45	3.94	6.88	1.75
1.2.9.1	001001	32	0.64	1	0.00	1.00	0.00	0.79	3.51	4.83	1.38
1.2.9.2	001001	32	4.07	2	1.00	1.00	0.00	2.04	4.32	16.06	3.72
2.3.1.1	041012	80	2.06	3	2.00	1.00	1.00	2.56	4.66	26.24	5.64
2.3.2.1	041011	80	0.11	0	0.00	1.00	0.00	0.52	3.34	7.01	2.10
1.2.8.2	009001	32	0.31	1	0.00	1.00	0.00	0.71	3.46	3.89	1.13
2.3.2.3	041011	65	0.08	0	0.00	0.00	0.00	0.02	3.01	5.57	1.85
2.3.3.1	041010	80	2.07	2	1.00	0.00	0.00	1.09	3.70	24.92	6.73
2.3.3.2	041010	65	0.09	0	0.00	0.00	0.00	0.02	3.01	5.67	1.88
2.3.4.1	041009	80	0.98	4	0.00	0.00	0.00	0.79	3.51	14.67	4.18
2.3.6.1	051001	65	0.41	2	0.00	0.00	0.00	0.38	3.25	7.91	2.44
2.3.4.2	041009	80	0.21	0	0.00	1.00	2.00	1.55	4.00	7.83	1.96
2.3.6.2	051001	65	0.95	1	0.00	1.00	0.00	0.86	3.55	11.53	3.24
2.3.5.1	037001	80	0.25	0	0.00	0.00	2.00	1.06	3.68	8.17	2.22
1.1.2.2	013001	32	0.22	1	0.00	1.00	1.00	1.19	3.77	3.64	0.97
2.3.7.2	105001	80	1.09	0	0.00	0.00	0.00	0.25	3.16	15.02	4.75
2.3.8.1	105002	80	0.11	0	0.00	1.00	0.00	0.52	3.34	7.01	2.10
2.3.8.2	105002	80	0.16	1	0.00	0.00	2.00	1.18	3.76	7.44	1.98
2.3.9.1	115001	32	1.68	4	0.00	0.00	0.00	0.95	3.62	10.46	2.89
2.3.9.2	115002	32	0.64	1	0.00	2.00	1.00	1.79	4.16	5.75	1.38
2.3.10.1	005004	32	1.82	3	2.00	0.00	0.00	1.51	3.97	11.97	3.01
2.3.10.2	005004	32	2.72	5	0.00	0.00	0.00	1.33	3.86	15.31	3.97

B

8 Annex

Space relationship diagrams



9 Annex

Risk analysis and risk responses

Table C.1: Impact factors computed by Guedes Soares and Gomes Lopes method [15]

WBS	Identified Risk	Objectives			Quality	Time	Cost	Impact Factor
		Quality	Delay	Costs				
1	DESIGN							
1.1	Poor identification of equipment and outfitting components forming in modular block		x	x	0	3	3	6
1.2	Lack of preliminary and further studies in outfitting modular implementation strategy		x	x	0	2	2	4
1.3	Unexperienced designers on conceptual production manufacturing		x	x	0	2	1	3
1.4	New procedures and techniques			x	0		1	1
1.5	Inadequate working plans, production and detail drawings		x	x	0	2	3	5
1.6	Inadequate inspection and control methodology	x	x	x	3	1	1	5
2	MODULE PARTS MANUFACTURED							
2.1	Equipment and raw material delivery out of date		x		0	2	0	2
2.2	Piping elements and structural elements, out of forms and dimensions	x	x		3	2	0	5
2.3	Welding joints faults	x	x		3	1	0	4
2.4	Equipment delivery without running tests		x	x	0	2	2	4
3	MODULE ASSEMBLY							
3.1	Parts out of dimensions	x	x	x	3	2	1	6
3.2	Parts out of shapes	x	x	x	3	2	1	6
3.3	Components missing		x		0	3	0	3
3.4	Components missaligned	x	x		0	3	0	3
4	DIMENSIONAL CONTROL AND RUNNING TESTS IN SHOP							
4.1	Module isometric check points out of tolerance in the three-dimensional measurement	x			3		0	3
4.2	Hydraulic tests failure due to leakages	x	x		2	2	0	4
5	MODULE TRANSPORTATION AND FITTING ON BLOCK							
5.1	Overloading for available hoisting equipment	x	x		0	1	2	3
5.2	Laid-up and laid-down small failures		x		0	1	0	1
5.3	Handling operation performed without qualified people	x	x		3	2	0	5
5.4	Misjudgment of boundary spaces offsets (interferences)	x	x	x	2	1	1	4
5.5	Schedule coordination between Block and Module Block failue	x	x		0	3	3	6
5.6	Components damages	x	x		0	2	1	3
6	ON BLOCK ASSEMBLING							
6.1	Parts out of dimensions	x	x	x	3	2	1	6
6.2	Parts out of shapes	x	x	x	3	2	1	6
6.3	Components missing		x		0	3	0	3
6.4	Block isometric check points for installing block module out of tolerances	x	x		1	2	0	3
6.5	Block isometric check points for piping connection out of tolerances	x	x		1	2	0	3
7	FINAL TRIALS FAILURE		x	x	0	2	2	4

Table C.2: Risk Response Acceptance (A), Mitigation (M), Transfer (T) and Avoidance (I).

CRITICAL SUCCESS FACTORS	1	DESIGN	Likelihood	Impact	Risk Factor	Risk Response
F1	1.1	Poor identification of equipment and outfitting components forming in modular block	2	5	10	M
F6 F7	1.2	Lack of preliminary and further studies in outfitting modular implementation strategy	4	4	16	M
F2	1.3	Unexperienced designers on conceptual production manufacturing	2	3	6	M
	1.4	New procedures and techniques	2	1	2	A
F2	1.5	Inadequate working plans, production and detail drawings	4	5	20	T
F2	1.6	Inadequate inspection and control methodology	1	5	5	M
	2	MODULE PARTS MANUFACTURED				
F3 F4	2.1	Equipment and raw material delivery out of date	5	2	10	M
F8 F9	2.2	Piping elements and structural elements, out of forms and dimensions	1	5	5	M
F8 F9	2.3	Welding joints faults	2	4	8	M
F8 F9	2.4	Equipment delivery without running tests	1	4	4	M
	3	MODULE ASSEMBLY				
F8 F9	3.1	Parts out of dimensions	1	5	5	M
F8 F9	3.2	Parts out of shapes	1	5	5	M
F3 F4	3.3	Components missing	3	3	9	M
F8 F9	3.4	Components misaligned	3	3	9	M
	4	DIMENSIONAL CONTROL AND RUNNING TESTS IN SHOP				
F8 F9	4.1	Module isometric check points out of tolerance in the three-dimensional measurement	5	3	15	M
F8 F9	4.2	Hydraulic tests failure due to leakages	4	4	16	M
	5	MODULE TRANSPORTATION AND FITTING ON BLOCK				
F8 F9	5.1	Overloading for available hoisting equipment	2	3	6	M
F8 F9	5.2	Laid-up and laid-down small failures	2	1	2	A
F8 F9	5.3	Handling operation performed without qualified people	2	5	10	M
F8 F9	5.4	Misjudgment of boundary spaces offsets (interferences)	4	4	16	M
F8 F9 F3 F4	5.5	Schedule coordination between Block and Module Block failure	5	5	25	I
F8 F9	5.6	Components damages	5	3	15	M
	6	ON BLOCK ASSEMBLING				
	6.1	Parts out of dimensions	4	5	20	T
F8 F9	6.2	Parts out of shapes	4	5	20	T
F8 F9	6.3	Components missing	4	3	12	M
F8 F9	6.4	Block isometric check points for installing block module out of tolerances	4	3	12	M
F8 F9 F8 F9	6.5	Block isometric check points for piping connection out of tolerances	4	3	12	M
F8 F9	7	FINAL TRIALS FAILURE	2	4	8	M

